

State	Model	Product Description	Product Code	Wastequip List Price	Sourcewell Member Special Market Price
FL	154693	40 Cubic Yard Heavy Duty Rectangular Roll Off Container 22' Long - Floor: 1/4" with 3" structural channels on 18" centers and 6" x 2" x 1/4" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 24" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 9,095.93	\$ 7,458.23
FL	155254	40 Cubic Yard Standard Duty Rectangular Roll Off Container 22' Long - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 8,025.76	\$ 6,580.67
FL	159897	20 Cubic Yard Standard Duty Bathtub ROC 22' Long - Floor: 7 gauge with 3" structural channels on 18" centers and 6"x2"x 3/16" Structural Tubing Main Rails, Walls: 10 gauge with 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 6,232.53	\$ 5,110.86
FL	159899	30 Cubic Yard Standard Duty Bathtub ROC 22' Long - Floor: 7 gauge with 3" structural channels on 18" centers and 6"x2"x 3/16" Structural Tubing Main Rails, Walls: 10 gauge with 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 6,807.27	\$ 5,581.57
FL	159901	40 Cubic Yard Standard Duty Bathtub ROC 22' Long - Floor: 7 gauge with 3" structural channels on 18" centers and 6"x 2"x 3/16" Structural Tubing Main Rails, Walls: 10 gauge with 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 7,985.59	\$ 6,547.71
FL	163340	20 Cubic Yard Heavy Duty Bathtub ROC 22' Long - Floor: 1/4" with 3" structural channels on 18" centers and 6" x 2" x 1/4" Structural Tubing Main Rails, Walls: 7 gauge with 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 7,707.49	\$ 6,320.08
FL	163361	30 Cubic Yard Heavy Duty Bathtub ROC 22' Long - Floor: 1/4" with 3" structural channels on 18" centers and 6" x 2" x 1/4" Structural Tubing Main Rails, Walls: 7 gauge two 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 8,852.85	\$ 7,259.44
FL	163375	40 Cubic Yard Heavy Duty Bathtub ROC 22' Long - Floor: 1/4" with 3" structural channels on 18" centers and 6" x 2" x 1/4" Structural Tubing Main Rails, Walls: 7 gauge with 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 10,152.71	\$ 8,325.49
FL	Container - Specialty ROC	Special ROC - FL (See Details for Product Information)	Roll Off Containers	Price On Demand	Price On Demand
FL	REC_10YD12FT_WQ_SD	10 YD Std. Duty Rect. Open Top ROC x 12' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 4,942.97	\$ 4,053.05
FL	REC_12YD12FT_WQ_SD	12 YD Std. Duty Rect. Open Top ROC x 12' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 5,207.68	\$ 4,270.38
FL	REC_15YD12FT_WQ_SD	15 YD Std. Duty Rect. Open Top ROC x 12' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 5,590.84	\$ 4,584.53
FL	REC_10YD14FT_WQ_SD	10 YD Std. Duty Rect. Open Top ROC x 14' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 5,176.78	\$ 4,244.63
FL	REC_12YD14FT_WQ_SD	12 YD Std. Duty Rect. Open Top ROC x 14' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 5,450.76	\$ 4,469.17
FL	REC_15YD14FT_WQ_SD	15 YD Std. Duty Rect. Open Top ROC x 14' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 5,809.20	\$ 4,763.75
FL	REC_12YD16FT_WQ_SD	12 YD Std. Duty Rect. Open Top ROC x 16' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 5,783.45	\$ 4,742.12
FL	REC_15YD16FT_WQ_SD	15 YD Std. Duty Rect. Open Top ROC x 16' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 12 gauge with side columns on 36" centers and 3" x 4" x 11 gauge Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 6,067.73	\$ 4,975.93
FL	TUB_10YD12FT_WQ_SD	10 YD Std. Duty Bath Tub Open Top ROC x 12' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 10 gauge with 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 4,986.23	\$ 4,089.10
FL	TUB_12YD12FT_WQ_SD	12 YD Std. Duty Bath Tub Open Top ROC x 12' interior length - Floor: 7 gauge with 3" structural channels on 18" centers and 6" x 2" x 3/16" Structural Tubing Main Rails, Walls: 10 gauge with 4" x 3" x 3/16" Top Rails, Primed and Painted any Standard Color	Roll Off Containers	\$ 5,192.23	\$ 4,258.02



State	Model	Product Description	Product Code	Wastequip List Price	Sourcwell Member Special Market Price
FL	190413	SIGN PLATE - 38 X 72 (2 per roll-off)	Side Upgrade	\$ 293.55	\$ 293.55
FL	192408	SIGN PLATE - 24 X 72 (2 per roll-off)	Side Upgrade	\$ 185.40	\$ 185.40
FL	194318	SIGN PLATE - 24 X 48 (2 per roll-off)	Side Upgrade	\$ 123.60	\$ 123.60
FL	197788	SIGN PLATE - 48 X 60 (2 per roll-off)	Side Upgrade	\$ 307.97	\$ 307.97
FL	207934	SIGN PLATE - 30 X 72 (2 per roll-off)	Side Upgrade	\$ 231.75	\$ 231.75
FL	213783	SIGN PLATE - 30 X 96 (2 per roll-off)	Side Upgrade	\$ 307.97	\$ 307.97
FL	213834	SIGN PLATE - 38 X 96 (2 per roll-off)	Side Upgrade	\$ 390.37	\$ 390.37
FL	228815	SIGN PLATE - 28 X 48 (2 per roll-off)	Side Upgrade	\$ 144.20	\$ 144.20
FL	234496	SIGN PLATE - 56 1/2 X 80 (2 per roll-off)	Side Upgrade	\$ 484.10	\$ 484.10
FL	234517	SIGN PLATE - 31 X 106 (2 per roll-off)	Side Upgrade	\$ 352.26	\$ 352.26
FL	235296	SIGN PLATE - 24 X 54 (2 per roll-off)	Side Upgrade	\$ 139.05	\$ 139.05
FL	235300	SIGN PLATE - 18 x 26 (2 per roll-off)	Side Upgrade	\$ 50.47	\$ 50.47
FL	237930	SIGN PLATE - 21 X 27 (2 per roll-off)	Side Upgrade	\$ 61.80	\$ 61.80
FL	238879	SIGN PLATE - 32 X 48 (2 per roll-off)	Side Upgrade	\$ 164.80	\$ 164.80
FL	239160	SIGN PLATE - 22 X 24 (2 per roll-off)	Side Upgrade	\$ 56.65	\$ 56.65
FL	239938	SIGN PLATE - 24 X 108 (2 per roll-off)	Side Upgrade	\$ 278.10	\$ 278.10
FL	241331	SIGN PLATE - 18 X 72 (2 per roll-off)	Side Upgrade	\$ 139.05	\$ 139.05
FL	244400	SIGN PLATE - 24 X 52 (2 per roll-off)	Side Upgrade	\$ 134.93	\$ 134.93
FL	245236	SIGN PLATE - 28 X 46 (2 per roll-off)	Side Upgrade	\$ 138.02	\$ 138.02
FL	247460	SIGN PLATE - 48 X 58 (2 per roll-off)	Side Upgrade	\$ 297.67	\$ 297.67
FL	250964	SIGN PLATE - 18 X 44 (2 per roll-off)	Side Upgrade	\$ 85.49	\$ 85.49
FL	251104	SIGN PLATE - 27 X 40 (2 per roll-off)	Side Upgrade	\$ 116.39	\$ 116.39
FL	252271	SIGN PLATE - 20 X 26 (2 per roll-off)	Side Upgrade	\$ 55.62	\$ 55.62
FL	254740	SIGN PLATE - 39 X 72 (2 per roll-off)	Side Upgrade	\$ 301.79	\$ 301.79
FL	257728	SIGN PLATE - 24 X 82 (2 per roll-off)	Side Upgrade	\$ 211.15	\$ 211.15
FL	257751	SIGN PLATE - 18 X 36 (2 per roll-off)	Side Upgrade	\$ 70.04	\$ 70.04
FL	272544	SIGN PLATE - 36 X 144 (2 per roll-off)	Side Upgrade	\$ 555.17	\$ 555.17
FL	FEL001	Slot - 6" High x 60" Wide Framed, Installed	Slot Options	\$ 84.46	\$ 84.46
FL	FEL002	Special Slot Option	Slot Options	Price On Demand	Price On Demand
FL	ROC101	Floor Upgrade - 22' 1/4" from 7ga Rectangle	Substructure Upgrade	\$ 425.39	\$ 425.39
FL	ROC102	Floor Upgrade - 22' 1/4" from 7ga Bathtub	Substructure Upgrade	\$ 390.37	\$ 390.37
FL	ROC103	Crossmember Upgrade - 22' 12" Spacing from 18"	Substructure Upgrade	\$ 269.86	\$ 269.86
FL	ROC104	Crossmember Upgrade - 22' 16" Spacing from 18"	Substructure Upgrade	\$ 125.66	\$ 125.66
FL	ROC105	Main Rail Upgrade - 22' 6" x 2" x 3/8" from 3/16"	Substructure Upgrade	\$ 615.94	\$ 615.94
FL	ROC106	Main Rail Upgrade - 22' 6" x 2" x 1/4" from 3/16"	Substructure Upgrade	\$ 162.74	\$ 162.74
FL	ROC107	Main Rail Upgrade - 20' 6" x 2" x 3/8" from 3/16"	Substructure Upgrade	\$ 587.10	\$ 587.10
FL	ROC108	Main Rail Upgrade - 20' 6" x 2" x 1/4" from 3/16"	Substructure Upgrade	\$ 148.32	\$ 148.32
FL	ROC109	Front Rollers - (Use where front rollers are not standard)	Substructure Upgrade	\$ 253.38	\$ 253.38
FL	ROC110	Substructure Upgrade - Special Requirement	Substructure Upgrade	Price On Demand	Price On Demand
FL	ROC501	Tarp Options - Side to Side Roll Tarp, Installed- Mountain Tarp Brand	Tarp Options	\$ 1,356.51	\$ 1,356.51
FL	ROC502	Tarp Options - Rear Opening Diaper, Installed	Tarp Options	\$ 401.70	\$ 401.70
FL	ROC301	Understructures - 61 3/4" Hooklift	Understructures	\$ 516.03	\$ 516.03
FL	ROC302	Understructures - 54" Hooklift	Understructures	\$ 488.22	\$ 488.22
FL	ROC303	Understructures - Heil Hook	Understructures	\$ 665.38	\$ 665.38
FL	ROC304	Understructures - Dempster Dino	Understructures	\$ 2,054.85	\$ 2,054.85
FL	ROC307	Understructures - Special Requirement	Understructures	Price On Demand	Price On Demand
FL	ROC308	Understructures - 36" Hooklift (verify Make/Model of Hoist)	Understructures	\$ 357.41	\$ 357.41
LA	262973	Special 40 YD HD Octagton Receiver - rated up to 100k packing force x 22' Long - Floor: 1/4" with 3" structural channels on 16" centers and 6"x 2"x 1/4" Structural Tubing Main Rails, Walls: 7 gauge lower and 10 gauge upper, Roof & Door Sheet 10 gauge, Door Frame 4 x 3 x 3/16", (2) Belly Bands, Ratchet Operated Latching System. Wheels: (2), Primed and Painted any Standard Color	Receiver Boxes	\$ 14,151.17	\$ 11,603.98
LA	OPR_40YD22FT_WQ_XHD	Special 40 YD XHD Octagton Receiver - rated up to 130k packing force x 22' Long - Floor: 1/4" with 3" structural channels on 12" centers and 6"x 2"x 3/8" Structural Tubing Main Rails, Walls: 7 gauge lower and upper, Roof & Door Sheet 7 gauge, Door Frame 4 x 3 x 3/16", (3) Belly Bands, Ratchet Operated Latching System. Wheels: (2), Primed and Painted any Standard Color	Receiver Boxes	\$ 16,321.38	\$ 13,383.82
LA	207374	2 YD HD FEL Apartment Compactor Receiver Container - 7 ga. bottom & 10 ga. body, 6" x 2" Polyurethane Casters (2) Swivel & (2) Rigid with Quick Release Caster pads, Compactor Opening on each - 27 1/2" High x 33" Wide, Primed and Painted any Standard Color	Receiver Boxes	\$ 3,156.95	\$ 2,588.39
LA	221431	3 YD HD FEL Apartment Compactor Receiver Container - 7 ga. bottom & 10 ga. body, 6" x 2" Polyurethane Casters (2) Swivel & (2) Rigid with Quick Release Caster pads, Compactor Opening on each - 27 1/2" High x 33" Wide, Primed and Painted any Standard Color	Receiver Boxes	\$ 3,602.94	\$ 2,954.04
LA	273830	2 YD HD REL Apartment Compactor Receiver Container - 1 1/4" Diameter Trunnion Bar, 10 ga. bottom & 10 ga. body, 6" x 2" Polyurethane Casters (2) Swivel & (2) Rigid with Quick Release Caster pads, Compactor Opening on each - 27 1/2" High x 33" Wide, Primed and Painted any Standard Color	Receiver Boxes	\$ 3,388.70	\$ 2,778.94