



---

**CLEARWATER**

**BRIGHT AND BEAUTIFUL • BAY TO BEACH**

---

**CITY OF CLEARWATER  
NEW CITY HALL**

100 South Myrtle Avenue  
Clearwater, FL 33756  
Ajax Job: 50000230

**GUARANTEED MAXIMUM PRICE  
PROPOSAL - FINAL**

September 21, 2024



Ajax Building Company, LLC  
109 Commerce Blvd.  
Oldsmar, FL 34677

## **TABLE OF CONTENTS**

- I. Executive Summary
- II. List of Documents
- III. Description of Work
  - A. Clarifications, Qualifications and Assumptions
- IV. GMP Cost Summary
  - A. GMP Cost Narrative
  - B. GMP Cost Report – Base Bid GMP (CM Summary Report)
  - C. GMP Cost Report – Base Bid GMP (CM Detail Report)
  - D. Allowance Schedule
  - E. Alternates
  - F. General Conditions and General Requirements Breakdown
  - G. CM Fee Calculation Check Sheet
- V. Logistics Plan
  - A. Logistics Plan Narrative
  - B. Logistics Plan
- VI. Project Schedule
  - A. Project Schedule Narrative
  - B. Project Schedule

## **EXECUTIVE SUMMARY**

Ajax Building Company, LLC is pleased to present this Guaranteed Maximum Price (GMP) Proposal No. 2 - Final for the Clearwater City Hall project for consideration by The City of Clearwater. This GMP Proposal No. 2 Clearwater City Hall represents the second and final cumulative GMP Proposal for this multi-GMP project.

Included within this GMP Proposal are cost reports, schedule and other project information to be utilized by the project team as the project moves forward. This GMP Proposal, upon acceptance by The City of Clearwater is intended to serve as the basis for an Amendment to the CM Contract, adding the next portion of work to the current contract.

### Project Description

The project consists of the construction of a new two-story City Hall on an approximately 1.68-acre site in downtown Clearwater. The two-story building is approximately 40,303 square feet modern facility to accommodate multiple City departments including the City Council, City Manager and City Attorney. The building will also house the new City Council Chambers. The building structure will be a composite steel system, metal framed exterior walls, cast-in-place shear walls and elevator shafts, and a metal panel exterior skin. The site development includes all hardscape including pervious concrete paving, park elements, storm draining to water gardens (ponds), and all associate MEP site elements. The project will be seeking LEED Silver Certification from the US Green Building Council.

### Realized Value Added Savings

Throughout the plan development and budgeting phases of this project, The City of Clearwater, Ajax, Wannamacher Jensen and the countless construction consultants worked in collaboration to review and modify the construction documents to provide the highest value for the available budget. Some of the highlights of this process are visible in the materials used for the metal façade paneling, roofing assembly design, selective use of both storefront and curtainwall at the exterior of the building, the inclusion of smoke rated glass and drywall partitions within the building, updated designs for the north and south facades to include additional exterior framing, the selection of interior finishes, the relocation of mechanical units to reduce quantity of structural steel and reduce the sound transmittance into the council chambers, the procurement and early release of mechanical equipment and generator, the inclusion of a plug in option for additional generator service beyond the capacity of the included emergency generator, and the reduction of soil exports from the site. This cooperative effort amongst all members of the Project Team has reduced the initially proposed construction costs in excess of \$4,000,000 which has produced the presented GMP Value stated in this proposal.

### Previously Accepted GMP Proposals

The following GMP Proposals have been previously accepted and are currently included in the Agreement between Ajax Building Company, LLC and The City of Clearwater.

GMP Proposal No. 1 Early Release: Includes the new City Hall Sitework & Utilities, Cast-in-Place Concrete Foundations and Foundation Walls, and General Conditions for the project in its entirety. Procurement of Elevators, Chillers, Electrical Switchgear, Panels and Generator equipment is also included due to extensive lead times from manufacturers for this material

The current Contract Sum, inclusive of the previously accepted GMP Proposals and Contract Amendments to date, totals \$7,407,439.

Current GMP Proposal - GMP Proposal No. 2 Final

This GMP Proposal No. 2 Final includes the balance of the work for the new Clearwater City Hall which represents the balance of work to be awarded on this multi-GMP project. Ajax Building Company, LLC is confident that the GMP costs included herein are representative of the proposed scope of work depicted in the GMP Documents. The work included in this GMP Proposal is based upon the List of Documents included in Section II of this proposal as amended by 1) the Clarifications, Qualifications, and Assumptions and 2) the Allowance Schedule, contained in Sections III and IV of this proposal.

This GMP Proposal No. 2 Final cumulative total is **\$29,605,458**. Upon acceptance, the cumulative Contract Sum will be \$29,605,458, inclusive of this GMP Proposal, previously accepted GMP Proposals, and Contract Amendments to date. The increase for the GMP Amendment 2 is calculated as follows:

• GMP 2 Final cumulative total	\$29,605,458
• GMP 1 ERP total / Amendment No. 1	<u>(\$7,407,439)</u>
• Amendment No. 2 Total	<b>\$22,198,019</b>

The Construction Manager's Preconstruction Phase Services is not included in the GMP Proposal. Per Contract, the CM Preconstruction Phase Services total \$369,965. This Preconstruction Phase fee included \$269,360 allocated to the City Hall project (22-0019-EN) and the remaining \$100,605 to the MSB Renovation project (23-0035-EN).

Note: The GMP Proposals presented by Ajax Building Company, LLC are cumulative and are not independent of one another.

In addition to the base GMP Proposal, Ajax Building Company, LLC has provided pricing for various Alternates in Section IV-F of this proposal for consideration by City of Clearwater. At this time, none of these Alternates are included within the base GMP Proposal. The following is a summary of the Alternates:

▪ Alternate No. 1 – PV Panels & Sacrificial Roof at Solar Array	Add	<b>\$333,056</b>
---	-----	------------------

Project Schedule

The project schedule included within this proposal is based on the information represented in the GMP Documents. The project schedule reflects an overall duration of twenty-two (22) months for the construction phase of the project.

The following contractual dates are incorporated into the CM Contract via this GMP Proposal.

▪ Substantial Completion	June 8, 2026
▪ Final Completion	September 1, 2026

The following additional Milestone Dates are anticipated within the project schedule in order to achieve the contractual dates listed above.

▪ Mobilization / Start of Construction	September 30, 2024
▪ Top-Out of Building Structure	June 12, 2025
▪ Building Dry-In	November 10, 2025
▪ Permanent Power	November 19, 2025
▪ Owner Occupancy	August 24, 2026

In order for Mobilization activities to commence on September 30, 2024 as scheduled, the following contractual activities will need to be completed as indicated.

- |                                  |                    |
|----------------------------------|--------------------|
| ▪ GMP Negotiations Complete      | September 23, 2024 |
| ▪ CM Contract Amendment Executed | October 3, 2024    |
| ▪ Notice to Proceed Issued       | October 4, 2024    |
| ▪ All Required Permits Issued    | October 11, 2024   |

In order to expedite the project start-up activities, the Design Team, the Construction Manager and the Owner will be required to closely coordinate and expedite submittal review/approval, respond to information requests, respond to conflicts/unforeseen conditions, etc.

## **LIST OF DOCUMENTS**

The work included in this GMP Proposal is based upon the List of Documents immediately following this narrative subject to amendments by 1) the Clarifications, Qualifications, and Assumptions and 2) the Allowance Schedule, contained in Sections III and IV of this proposal.

The List of Documents includes the:

- Contract Drawings
- Project Specifications
- Addenda Issued by the Architect / Engineer
- Pre-Bid Requests for Information (Pre-Bid RFI's)
- Other Documents (As Listed)
- Bid Packages and Bid Package Addenda

**CONTRACT DRAWINGS**

**Entitled CLEARWATER CITY HALL – Permit Set dated 07/05/2024**

<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
	<b>Cover and Index Sheets</b>			
	Cover Sheet	7/5/24		
G-101	DRAWING LEGEND AND BUILDING DATA	7/5/24		
G-102	INDEX SHEET	7/5/24	8/2/24	
G-103	CODE ANALYSIS	7/5/24		
G-104	MOUNTING HEIGHTS	7/5/24		
G-105	UL LISTINGS	7/5/24		
	<b>Life Safety</b>			
B-101	LEVEL 1 - LIFE SAFETY PLAN	7/5/24		
B-102	LEVEL 2 - LIFE SAFETY PLAN	7/5/24		
	<b>Interior</b>			
ID-101	LEVEL 1 - FINISH PLAN	7/5/24		
ID-102	LEVEL 2 - FINISH PLAN	7/5/24		
ID-110	FINISH LEGEND	7/5/24		
ID-201	LEVEL 1 - FURNITURE PLAN	7/5/24		
ID-202	LEVEL 2 - FURNITURE PLAN	7/5/24		
ID-301	LEVEL 1 - EQUIPMENT PLAN	7/5/24		
ID-302	LEVEL 2 - EQUIPMENT PLAN	7/5/24		
ID-401	INTERIOR DETAILS	7/5/24		
ID-402	INTERIOR DETAILS	7/5/24		
ID-403	INTERIOR DETAILS	7/5/24		
ID-404	CHAMBER WALL DETAILS	7/5/24		
ID-405	CHAMBER WALL DETAILS	7/5/24		
ID-406	CHAMBER WALL DETAILS	7/5/24		
ID-407	CHAMBER WALL DETAILS	7/5/24		
	<b>Civil</b>			
C1.01	GENERAL NOTES	7/5/24		

<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
C1.02	STORMWATER POLLUTION PREVENTION PLAN	7/5/24		
C1.03	STORMWATER PREVENTION NOTES	7/5/24		
C1.04	EROSION CONTROL DETAILS	7/5/24		
C1.05	TREE PROTECTION PLAN	7/5/24		
C2.00	DEMOLITION PLAN	7/5/24		
C3.00	OVERALL SITE PLAN	7/5/24		
C3.01	SITE PLAN	7/5/24		
C3.02	CURB RAMP DETAILS	7/5/24		
C3.03	SOLID WASTE TRUCK - TURNING ANALYSIS	7/5/24		
C3.04	DELIVERY VEHICLE TRUCK - TURNING ANALYSIS	7/5/24		
C3.05	FIRE TRUCK - TURNING ANALYSIS	7/5/24		
C3.06	PASSENGER CAR - TURNING ANALYSIS	7/5/24		
C3.10	HORIZONTAL CONTROL PLAN	7/5/24		
C3.11	CONCRETE CONTROL PLAN	7/5/24		
C4.00	SITE GRADING PLAN	7/5/24		
C4.01	GRADING PLAN ENLARGED VIEWS	7/5/24		
C5.00	SITE DRAINAGE PLAN	7/5/24		
C5.01	RAIN GARDEN CROSS SECTIONS	7/5/24		
C6.00	MASTER UTILITY PLAN	7/5/24		
C6.01	SITE UTILITY PLAN	7/5/24		
C7.00	SITE DETAILS	7/5/24		
C7.01	SITE AND STORM DETAILS	7/5/24		
C7.02	UTILITY DETAILS (1)	7/5/24		
C7.03	UTILITY DETAILS (2)	7/5/24		
	<b>Landscaping</b>			
LI-101	IRRIGATION PLAN	7/5/24		
LI-501	IRRIGATION DETAILS	7/5/24		
LS-00	SOILS PLAN	7/5/24		
LS-01	LANDSCAPE PLAN	7/5/24		



<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
LS-02	LANDSCAPE NOTES	7/5/24		
LS-03	LANDSCAPE DETAILS (1)	7/5/24		
LS-04	LANDSCAPE DETAILS (2)	7/5/24		
	<b>Structural</b>			
S-101	GENERAL STRUCTURAL NOTES	7/5/24		
S-102	WIND DESIGN DATA	7/5/24		
S-103	LOAD PLANS & SCHEDULES	7/5/24		
S-104	OVERALL ISOMETRIC VIEWS	7/5/24		
S-201	OVERALL FOUNDATION PLAN	7/5/24		
S-201A	PARTIAL FOUNDATION PLAN - AREA A	7/5/24		
S-201B	PARTIAL FOUNDATION PLAN - AREA B	7/5/24		
S-202	OVERALL SLAB ON GRADE PLAN	7/5/24		
S-202A	PARTIAL SLAB ON GRADE PLAN - AREA A	7/5/24		
S-202B	PARTIAL SLAB ON GRADE PLAN - AREA B	7/5/24		
S-203	OVERALL LEVEL 2 FRAMING PLAN	7/5/24		
S-203A	PARTIAL LEVEL 2 FRAMING PLAN - AREA A	7/5/24		
S-203B	PARTIAL LEVEL 2 FRAMING PLAN - AREA B	7/5/24		
S-204	OVERALL ROOF FRAMING PLAN	7/5/24		
S-204A	PARTIAL ROOF FRAMING PLAN - AREA A	7/5/24		
S-204B	B PARTIAL ROOF FRAMING PLAN - AREA B	7/5/24		
S-205	OVERALL HIGH ROOF FRAMING PLAN	7/5/24		
S-205A	PARTIAL HIGH ROOF FRAMING PLAN - AREA A	7/5/24		
S-205B	PARTIAL HIGH ROOF FRAMING PLAN - AREA B	7/5/24		
S-206	PARTIAL CANOPY FRAMING PLAN - WEST CANOPY	7/5/24		
S-207	PARTIAL CANOPY FRAMING PLAN - EAST CANOPY	7/5/24		
S-301	TYPICAL DETAILS	7/5/24		
S-302	TYPICAL DETAILS	7/5/24		
S-303	TYPICAL DETAILS	7/5/24		
S-304	TYPICAL DETAILS	7/5/24		

<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
S-305	TYPICAL DETAILS	7/5/24		
S-306	TYPICAL DETAILS	7/5/24		
S-307	TYPICAL DETAILS	7/5/24		
S-308	TYPICAL DETAILS	7/5/24		
S-309	TYPICAL DETAILS	7/5/24		
S-401	SECTIONS & DETAILS	7/5/24		
S-402	SECTIONS & DETAILS	7/5/24		
S-403	SECTIONS & DETAILS	7/5/24		
S-404	SECTIONS & DETAILS	7/5/24		
S-405	SECTIONS & DETAILS	7/5/24		
S-406	SECTIONS & DETAILS	7/5/24		
S-407	SECTIONS & DETAILS	7/5/24		
S-408	WEST CANOPY FRAME DETAILS	7/5/24		
S-409	WEST CANOPY FRAME DETAILS	7/5/24		
S-410	EAST CANOPY FRAME DETAILS	7/5/24		
S-411	COLUMN GROUP 1 PLANS & DETAILS	7/5/24		
S-412	COLUMN GROUP 2 PLANS & DETAILS	7/5/24		
S-413	COLUMN GROUP 3 & GROUP 4 PLANS & DETAILS	7/5/24		
S-501	SHEAR WALL ELEVATIONS & DETAILS	7/5/24		
S-502	SHEAR WALL ELEVATIONS	7/5/24		
S-503	SHEAR WALL ELEVATIONS	7/5/24		
S-504	SHEAR WALL ELEVATIONS	7/5/24		
S-505	SHEAR WALL ELEVATIONS	7/5/24		
S-506	SHEAR WALL ELEVATIONS	7/5/24		
S-507	BUILDING ELEVATIONS - STEEL FRAMING	7/5/24		
S-508	ENLARGED BUILDING ELEVATIONS - STEEL FRAMING	7/5/24		
S-509	ENLARGED BUILDING ELEVATIONS - STEEL FRAMING	7/5/24		
S-510	ENLARGED BUILDING ELEVATIONS - STEEL FRAMING	7/5/24		
S-601	SCHEDULES	7/5/24		

<u>Sheet</u>	<u>Description</u>	<u>Date</u>	<u>Revised</u>	<u>Revised</u>
S-602	SCHEDULES	7/5/24		
S-701	FACADE MOCKUP DETAILS	8/2/24		
	<b>Architectural</b>			
A-001	SITE PLAN	7/5/24		
A-101	LEVEL 1 - FLOOR PLAN	7/5/24		
A-102	LEVEL 2 - FLOOR PLAN	7/5/24		
A-106	ROOF PLAN	7/5/24		
A-107	ALTERNATE ROOF PLAN	7/5/24		
A-110	EOS PLAN - LEVEL 1	7/5/24		
A-111	EOS PLAN - LEVEL 2	7/5/24		
A-118	LEVEL 1 - PARTITION TYPE PLAN	8/2/24		
A-119	LEVEL 2 - PARTITION TYPE PLAN	8/2/24		
A-120	LEVEL 1 - DIMENSION PLAN	7/5/24		
A-121	LEVEL 2-DIMENSION PLAN	7/5/24		
A-122	ROOF-DIMENSION PLAN	7/5/24		
A-201	LEVEL 1 - RCP	7/5/24		
A-202	LEVEL 2 - RCP	7/5/24		
A-203	ENLARGED RCP	7/5/24		
A-204	ENLARGED RCP	7/5/24		
A-301	EXTERIOR ELEVATIONS	7/5/24		
A-302	EXTERIOR ELEVATIONS	7/5/24		
A-303	EXTERIOR ENLARGED SIGNAGE	7/5/24		
A-304	AXONOMETRIC VIEWS	7/5/24		
A-310	BUILDING SECTIONS	7/5/24		
A-311	BUILDING SECTIONS	7/5/24		
A-401	ENLARGED WATER CLOSET PLANS AND ELEVATIONS	7/5/24		
A-402	ENLARGED WATER CLOSET PLANS AND ELEVATIONS	7/5/24		
A-403	ENLARGED WATER CLOSET PLANS AND ELEVATIONS	7/5/24		
A-404	ENLARGED WATER CLOSET PLANS AND ELEVATIONS	7/5/24		

<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
A-410	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-411	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-412	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-413	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-414	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-415	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-416	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-417	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-418	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-419	ENLARGED FLOOR PLANS AND INTERIOR ELEVATIONS	7/5/24		
A-420	MILLWORK SECTIONS	7/5/24		
A-421	MILLWORK SECTIONS	7/5/24		
A-422	MILLWORK SECTIONS	7/5/24		
A-501	INTERIOR ELEVATIONS	7/5/24		
A-502	INTERIOR ELEVATIONS	7/5/24		
A-503	INTERIOR ELEVATIONS	7/5/24		
A-504	INTERIOR ELEVATIONS	7/5/24		
A-505	INTERIOR ELEVATIONS	7/5/24		
A-601	ENLARGED STAIR PLANS AND SECTIONS	7/5/24		
A-602	ENLARGED STAIR PLANS AND SECTIONS	7/5/24		
A-603	ENLARGED STAIR PLANS AND SECTIONS	7/5/24		
A-604	ENLARGED STAIR PLANS AND SECTIONS	7/5/24		
A-605	STAIR DETAILS	7/5/24		
A-608	ENLARGED ELEVATOR A- PLANS AND SECTIONS	7/5/24		
A-609	ENLARGED ELEVATOR B - PLANS AND SECTIONS	7/5/24		
A-701	WALL SECTIONS	7/5/24		
A-702	WALL SECTIONS	7/5/24		
A-703	WALL SECTIONS	7/5/24		
A-704	WALL SECTIONS	7/5/24		

<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
A-705	WALL SECTIONS	7/5/24		
A-720	ENCLOSURE DETAILS	7/5/24		
A-721	ENCLOSURE DETAILS	7/5/24		
A-722	ENCLOSURE DETAILS	7/5/24		
A-723	ENCLOSURE DETAILS	7/5/24		
A-724	ENCLOSURE DETAILS	7/5/24		
A-725	ENCLOSURE DETAILS	7/5/24		
A-726	PLAN DETAILS	8/2/24		
A-730	CEILING DETAILS	7/5/24		
A-731	CEILING DETAILS	7/5/24		
A-800	PARTITION TYPES	7/5/24		
A-801	PARTITION TYPES	7/5/24		
A-802	PARTITION TYPES	7/5/24		
A-803	PARTITION TYPES	7/5/24		
A-804	PARTITION TYPES	7/5/24		
A-805	PARTITION DETAILS	7/5/24		
A-806	PARTITION DETAILS	7/5/24		
A-810	DOOR SCHEDULES	7/5/24		
A-811	DOOR DETAILS	7/5/24		
A-812	DOOR DETAILS	7/5/24		
A-813	DOOR DETAILS	7/5/24		
A-820	EXTERIOR STOREFRONT ELEVATIONS	7/5/24		
A-821	EXTERIOR STOREFRONT ELEVATIONS	7/5/24		
A-822	EXTERIOR CURTAIN WALL ELEVATIONS	7/5/24		
A-823	INTERIOR STOREFRONT ELEVATIONS	7/5/24	8/2/24	
A-824	INTERIOR STOREFRONT ENLARGED PLAN	7/5/24		
A-825	CURTAINWALL DETAILS	7/5/24		
A-827	EXTERIOR STOREFRONT DETAILS	7/5/24		
A-828	EXTERIOR STOREFRONT DETAILS	7/5/24		

<u>Sheet</u>	<u>Description</u>	<u>Date</u>	<u>Revised</u>	<u>Revised</u>
A-829	INTERIOR STOREFRONT DETAILS	7/5/24		
A-830	INTERIOR STOREFRONT DETAILS	7/5/24		
	<b>Fire Protection</b>			
F-000	NOTES, LEGENDS, AND ABBREVIATIONS	7/5/24		
F-001-F	SITE PLAN - FIRE PROTECTION	7/5/24		
F-101	1 LEVEL 1 - FIRE PROTECTION PLAN	7/5/24		
F-102	LEVEL 2 - FIRE PROTECTION PLAN	7/5/24		
F-103	ROOF FIRE PROTECTION PLAN	7/5/24		
F-501	FIRE PROTECTION DETAILS	7/5/24		
F-502	FIRE PROTECTION DETAILS	7/5/24		
	<b>Plumbing</b>			
P-000	NOTES, LEGENDS, AND ABBREVIATIONS	7/5/24		
P-100	UNDERGROUND FLOOR PLAN - PLUMBING	7/5/24		
P-101	LEVEL 1 - GRAVITY PLAN	7/5/24		
P-102	LEVEL 2 - GRAVITY PLAN	7/5/24		
P-103	ROOF - GRAVITY PLAN	7/5/24		
P-201	LEVEL 1 - PRESSURE PLAN	7/5/24	8/2/24	
P-202	LEVEL 2 - PRESSURE PLAN	7/5/24		
P-203	ROOF - PRESSURE PLAN	7/5/24		
P-301	GRAVITY ISOMETRIC OVERALL	7/5/24		
P-302	PRESSURE ISOMETRIC OVERALL	7/5/24	8/2/24	
P-303	STORM ISOMETRIC OVERALL	7/5/24		
P-501	PLUMBING DETAILS	7/5/24		
P-601	PLUMBING SCHEDULES	7/5/24	8/2/24	
	<b>Mechanical</b>			
M-000	NOTES, LEGENDS, AND ABBREVIATIONS	7/5/24		
M-101	LEVEL 1 - MECHANICAL PLAN	7/5/24		
M-102	LEVEL 2 - MECHANICAL PLAN	7/5/24		

<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
M-104	ROOF - MECHANICAL PLAN	7/5/24		
M-501	DETAILS	7/5/24		
M-502	DETAILS	7/5/24		
M-503	DETAILS	7/5/24		
M-601	SCHEDULES	7/5/24		
M-602	SCHEDULES	7/5/24		
	<b>Electrical</b>			
E-000	NOTES, LEGENDS, AND ABBREVIATIONS	7/5/24		
E-100	SITE PLAN - ELECTRICAL	7/5/24		
E-101	LEVEL 1 - LIGHTING PLAN	7/5/24		
E-101A	LEVEL 1- LIGHTING CONTROL PLAN	7/5/24		
E-102	LEVEL 2 - LIGHTING PLAN	7/5/24		
E-102A	LEVEL 2 - LIGHTING CONTROL PLAN	7/5/24		
E-201	LEVEL 1 - POWER PLAN	7/5/24		
E-202	LEVEL 2 - POWER PLAN	7/5/24		
E-203	ROOF ELECTRICAL PLAN	7/5/24		
E-501	ELECTRICAL DETAILS	7/5/24		
E-502	LIGHTING CONTROL DETAILS	7/5/24		
E-503	LIGHTING CONTROL DETAILS	7/5/24		
E-601	SCHEDULES	7/5/24		
E-602	SCHEDULES	7/5/24		
E-603	SCHEDULES	7/5/24		
E-604	SCHEDULES	7/5/24		
E-701	POWER RISER DIAGRAM	7/5/24		
	<b>Technology</b>			
T-000	NOTES, LEGENDS, AND ABBREVIATIONS	7/5/24		
T-001	NOTES, LEGENDS, AND ABBREVIATIONS	7/5/24		
T-100	SITE PLAN - TECHNOLOGY	7/5/24		
T-101	LEVEL 1 - TECHNOLOGY PLAN	7/5/24		

<b>Sheet</b>	<b>Description</b>	<b>Date</b>	<b>Revised</b>	<b>Revised</b>
T-102	LEVEL 2 - TECHNOLOGY PLAN	7/5/24		
T-103	ROOF TECHNOLOGY PLAN	7/5/24		
T-401	ENLARGED COMMON AREA PLANS	7/5/24		
T-501	DETAILS	7/5/24		
T-502	DETAILS	7/5/24		
T-503	DETAILS	7/5/24		
T-504	DETAILS	7/5/24		
T-505	DETAILS	7/5/24		
T-506	DETAILS	7/5/24		
T-601	RISERS	7/5/24		
	(END OF CONTRACT DRAWINGS)			



**PROJECT SPECIFICATIONS**

**Entitled Clearwater City Hall Permit Set dated 07/05/24**

<u>Section</u>	<u>Description</u>	<u># Pages</u>	<u>Date</u>	<u>Revised</u>
	<b>Table of Contents</b>			
TOC	Table of Contents	5	7/5/24	
	<b>Division 01 – General Requirements</b>			
011000	SUMMARY OF WORK	3	7/5/24	
012300	ALTERNATES	2	7/5/24	
012500	SUBSTITUTION PROCEDURES	3	7/5/24	
012600	CONTRACT MODIFICATION PROCEDURES	2	7/5/24	
012900	PAYMENT PROCEDURES	4	7/5/24	
013100	PROJECT MANAGEMENT AND COORDINATION	8	7/5/24	
013200	CONSTRUCTION PROGRESS DOCUMENTATION	8	7/5/24	
013233	PHOTOGRAPHIC DOCUMENTATION	3	7/5/24	
013300	SUBMITTAL PROCEDURES	8	7/5/24	
014000	QUALITY REQUIREMENTS	8	7/5/24	
014200	REFERENCES	8	7/5/24	
014529	STRUCTURAL TESTING AND INSPECTIONS	16	7/5/24	
015000	TEMPORARY FACILITIES AND CONTROLS	8	7/5/24	
015150	CONSTRUCTION INDOOR AIR QUALITY MANAGEMENT	8	7/5/24	
016000	PRODUCT REQUIREMENTS	4	7/5/24	
017300	EXECUTION	7	7/5/24	
017419	CONSTRUCTION WASTE MANAGEMENT	5	7/5/24	
017700	CLOSEOUT PROCEDURES	5	7/5/24	
017823	OPERATION AND MAINTENANCE DATA	6	7/5/24	
017836	WARRANTIES AND BONDS	2	7/5/24	
017839	PROJECT RECORD DOCUMENTS	4	7/5/24	
017900	DEMONSTRATION AND TRAINING	4	7/5/24	
018113	SUSTAINABLE DESIGN REQUIREMENTS	12	7/5/24	
019100	COMMISSIONING OF SYSTEMS	12	7/5/24	

<b>Section</b>	<b>Description</b>	<b># Pages</b>	<b>Date</b>	<b>Revised</b>
	<b>Division 02 – Existing Conditions</b>			
023200	GEOTECHNICAL DATA	1	7/5/24	
	<b>Division 03 – Concrete</b>			
031000	CONCRETE FORMING AND ACCESSORIES	7	7/5/24	
032900	VAPOR BARRIER	2	7/5/24	
033000	CAST-IN-PLACE CONCRETE	14	7/5/24	
	<b>Division 04 – Masonry</b>			
042000	UNIT MASONRY	5	7/5/24	
042200	REINFORCED UNIT MASONRY	3	7/5/24	
	<b>Division 05 – Metals</b>			
051200	STRUCTURAL STEEL FRAMING	8	7/5/24	
052100	STEEL JOIST FRAMING	2	7/5/24	
053000	METAL DECKING	3	7/5/24	
054100	STRUCTURAL STEEL STUDS	5	7/5/24	
055000	METAL FABRICATIONS	7	7/5/24	
055113	METAL PAN STAIRS	6	7/5/24	
055213	PIPE AND TUBE RAILINGS	6	7/5/24	
057313	DECORATIVE METAL RAILINGS	7	7/5/24	
	<b>Division 06 – Wood, Plastics and Composites</b>			
061000	ROUGH CARPENTRY	4	7/5/24	
061600	SHEATHING	4	7/5/24	
062023	INTERIOR FINISH CARPENTRY	5	7/5/24	
064116	PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS	5	7/5/24	
	<b>Division 07 – Thermal and Moisture Protection</b>			
071326	SELF-ADHERING SHEET WATERPROOFING	5	7/5/24	
071616	CRYSTALLINE WATERPROOFING	4	7/5/24	
072100	BUILDING INSULATION	4	7/5/24	
072713	MODIFIED BITUMINOUS SHEET AIR BARRIERS	3	7/5/24	
072726	FLUID-APPLIED MEMBRANE AIR BARRIERS	3	7/5/24	

<b>Section</b>	<b>Description</b>	<b># Pages</b>	<b>Date</b>	<b>Revised</b>
074213	FORMED METAL WALL PANELS	6	7/5/24	
075423	THERMOPLASTIC POLYOELFIN (TPO) MEMBRANE ROOFING	7	7/5/24	
076200	SHEET METAL FLASHING AND TRIM	7	7/5/24	
077100	ROOF SPECIALTIES	6	7/5/24	
077200	ROOF ACCESSORIES	4	7/5/24	
078100	APPLIED FIREPROOFING	5	7/5/24	
078413	PENETRATION FIRESTOPPING	6	7/5/24	
079200	PENETRATION FIRESTOPPING	7	7/5/24	
	<b>Division 08 – Openings</b>			
081113	HOLLOW METAL DOORS AND FRAMES	7	7/5/24	
081416	FLUSH WOOD DOORS	5	7/5/24	
083113	ACCESS DOORS AND FRAMES	2	7/5/24	
083323	OVERHEAD COILING DOORS	7	7/5/24	
084113	ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS	9	7/5/24	
084413	GLAZED ALUMINUM CURTAIN WALLS	7	7/5/24	
087100	DOOR HARDWARE	16	7/5/24	
087113	AUTOMATIC DOOR OPERATORS	2	8/2/24	
087913	KEY STORAGE EQUIPMENT	2	7/5/24	
088000	GLAZING	11	7/5/24	
089119	FIXED LOUVERS	6	7/5/24	
	<b>Division 09 – Finishes</b>			
092116	GYPSUM BOARD SHAFT WALL ASSEMBLIES	4	7/5/24	
092216	NON-STRUCTURAL METAL FRAMING	5	7/5/24	
092400	PORTLAND CEMENT PLASTERING	4	7/5/24	
092900	GYPSUM BOARD	6	7/5/24	
093013	CERAMIC TILING	4	7/5/24	
095113	ACOUSTICAL PANEL CEILINGS	5	7/5/24	
096513	RESILIENT BASE AND ACCESSORIES	3	7/5/24	
096519	RESILIENT TILE FLOORING	4	7/5/24	

<b>Section</b>	<b>Description</b>	<b># Pages</b>	<b>Date</b>	<b>Revised</b>
096536	STATIC-CONTROL RESILIENT FLOORING	5	7/5/24	
096813	TILE CARPETING	4	7/5/24	
096900	ACCESS FLOORING	5	7/5/24	
098433	SOUND-ABSORBING WALL UNITS	5	7/5/24	
098453	SOUND BARRIER MULLION TRIM CAPS	4	7/5/24	
099100	PAINTING	9	7/5/24	
	<b>Division 10 – Specialties</b>			
102600	WALL AND DOOR PROTECTION	3	7/5/24	
102800	TOILET ACCESSORIES	2	7/5/24	
104400	FIRE PROTECTION SPECIALTIES	5	7/5/24	
107316	METAL CANOPIES	4	7/5/24	
109050	MISCELLANEOUS SPECIALTIES	2	7/5/24	
	<b>Division 11 – Equipment</b>			
111319	STATIONARY LOADING DOCK EQUIPMENT	4	7/5/24	
113100	RESIDENTIAL APPLIANCES	3	7/5/24	
	<b>Division 12 – Furnishings</b>			
122413	ROLLER WINDOW SHADES	5	7/5/24	
123661	SIMULATED STONE COUNTERTOPS	2	7/5/24	
124813	ENTRANCE FLOOR MATS AND FRAMES	2	7/5/24	
	<b>Division 13 – Special Construction</b>			
	NOT USED			
	<b>Division 14 – Conveying Equipment</b>			
142123	MACHINE ROOM-LESS ELECTRIC TRACTION PASSENGER ELEVATORS	17	7/5/24	
	<b>Division 21 – Fire Suppression</b>			
210000	FIRE PROTECTION	19	7/5/24	
	<b>Division 22 – Plumbing</b>			
220000	PLUMBING	13	7/5/24	
220523	GENERAL-DUTY VALVES FOR PLUMBING PIPING	5	7/5/24	

<b>Section</b>	<b>Description</b>	<b># Pages</b>	<b>Date</b>	<b>Revised</b>
220529	HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT	5	7/5/24	
220530	SUPPORTS, ANCHORS AND SEALS - PLUMBING	8	7/5/24	
220553	IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT	3	7/5/24	
220700	PLUMBING INSULATION	5	7/5/24	
221000	INSTALLATION OF PIPING PLUMBING	4	7/5/24	
221001	NATURAL GAS PIPING SYSTEMS	4	7/5/24	
221100	PIPE, TUBE AND FITTINGS – PLUMBING	4	7/5/24	
221101	CONDENSATE PIPING SYSTEMS – PLUMBING	3	7/5/24	
221116	DOMESTIC WATER PIPING	6	7/5/24	
221123	DOMESTIC WATER PUMPS	2	7/5/24	
221316	SANITARY WASTE AND VENT PIPING	5	7/5/24	
221413	FACILITY STORM DRAINAGE PIPING	4	7/5/24	
223000	PLUMBING EQUIPMENT	3	7/5/24	
224000	PLUMBING FIXTURES	3	7/5/24	
	<b>Division 23 – HVAC</b>			
230000	HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)	14	7/5/24	
230513	ELECTRICAL COORDINATION	6	7/5/24	
230523	VALVES	6	7/5/24	
230530	SUPPRTS, ANCHORS AND SEALS	6	7/5/24	
230553	IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT	2	7/5/24	
230593	TESTING, ADJUSTING AND BALANCING	8	7/5/24	
230700	HVAC INSULATION	5	7/5/24	
230900	INSTRUMENTATION AND CONTROL FOR HVAC	17	7/5/24	
232100	INSTALLATION OF HVAC PIPING	4	7/5/24	
232101	HVAC PIPE, TUBE AND FITTINGS	6	7/5/24	
232113	CHILLED WATER PIPING SYSTEMS AND SPECIALTIES	19	7/5/24	
232115	CONDENSATE PIPING SYSTEMS	3	7/5/24	
232123	HVAC PUMPS	2	7/5/24	

<b>Section</b>	<b>Description</b>	<b># Pages</b>	<b>Date</b>	<b>Revised</b>
232300	REFRIGERANT PIPING SYSTEMS	5	7/5/24	
232500	HVAC WATER TREATMENT SYSTEM AND SERVICE	4	7/5/24	
233000	AIR DISTRIBUTION SYSTEM	13	7/5/24	
233400	HVAC FANS	3	7/5/24	
233600	VARIABLE AIR VOLUME BOXES	3	7/5/24	
233700	LOUVERS	3	7/5/24	
236400	AIR COOLED CHILLERS	6	7/5/24	
237300	CENTRAL STATION AIR HANDLING UNITS	16	7/5/24	
237400	AIR CONDITIONING UNITS	3	7/5/24	
	<b>Division 26 – Electrical</b>			
260100	BASIC ELECTRICAL REQUIREMENTS	11	7/5/24	
260519	LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS	3	7/5/24	
260526	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS	10	7/5/24	
260529	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS	5	7/5/24	
260533	RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS	10	7/5/24	
260553	ELECTRICAL IDENTIFICATION	8	7/5/24	
260572	OVERCURRENT PROTECTIVE DEVICE SHORT-CIRCUIT STUDY	7	7/5/24	
260573	OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY	9	7/5/24	
260800	COMMISSIONING OF ELECTRICAL	8	7/5/24	
260923	LIGHTING CONTROL DEVICES	5	7/5/24	
262200	LOW-VOLTAGE TRANSFORMERS	4	7/5/24	
262413	SWITCHBOARDS	7	7/5/24	
262416	PANELBOARDS	13	7/5/24	
262726	WIRING DEVICES	9	7/5/24	
262813	FUSES	2	7/5/24	
262816	ENCLOSED SWITCHES AND CIRCUIT BREAKERS	5	7/5/24	
263213	ENGINE GENERATORS	6	7/5/24	
263600	TRANSFER SWITCHES	6	7/5/24	
263601	GENERATOR DCKING STATION	3	7/5/24	

<b>Section</b>	<b>Description</b>	<b># Pages</b>	<b>Date</b>	<b>Revised</b>
264313	TRANSIENT-VOLTAGE SUPPRESSION FOR LOW-VOLTAGE ELECTRICAL POWER CIRCUITS	5	7/5/24	
265119	INTERIOR LIGHTING	7	7/5/24	
265600	EXTERIOR LIGHTING	3	7/5/24	
	<b>Division 27 – Communications</b>			
270010	TECHNOLOGY GENERAL PROVISIONS	16	7/5/24	
270526	GROUNDING AND BONDING FOR TELECOMMUNICATIONS SYSTEMS	8	7/5/24	
270528	RACEWAYS FOR TECHNOLOGY	15	7/5/24	
271000	STRUCTURED CABLING SYSTEM	17	7/5/24	
274100	AUDIO VISUAL SYSTEMS	34	7/5/24	
	<b>Division 28 – Electronic Safety and Security</b>			
283111	ADDRESSABLE FIRE ALARM SYSTEM	16	7/5/24	
	<b>Division 31 – Earthwork</b>			
313116	TERMITE CONTROL	3	7/5/24	
	<b>Appendix A</b>			
<b>SECTION I</b>	<b>ADVERTISEMENT OF BIDS &amp; NOTICE TO CONTRACTORS</b>	Not	Included	
<b>SECTION II</b>	<b>INSTRUCTIONS TO BIDDERS</b>	Not	Included	
<b>SECTION III</b>	<b>GENERAL CONDITIONS</b>	Not	Included	
<b>SECTION IV</b>	<b>TECHNICAL SPECIFICATIONS</b>	Not	Included	
<b>SECTION V</b>	<b>CONTRACT DOCUMENTS</b>	Not	Included	
	<b>(END OF PROJECT SPECIFICATIONS)</b>			



ADDENDA ISSUED BY THE ARCHITECT/ENGINEER

<u>Addenda #</u>	<u>Description</u>	<u># Pages</u>	<u>Date</u>	<u>Revised</u>
1	Addendum 1	10	8/2/2024	
	(END OF ADDENDA)			



**PRE-BID REQUESTS FOR INFORMATION (PRE-BID RFI's)**

<b><u>PB RFI No.</u></b>	<b><u>Description</u></b>	<b><u>Issued</u></b>	<b><u>Resp</u></b>	<b><u>Revised</u></b>
1	Electrical Transformer Nomenclatures	6/12/24	6/21/24	
2	Design Thickness Specification	7/18/24	7/23/24	
3	Gypsum Board Clarification	7/18/24	7/30/24	
4	Door Hardware Specification	7/22/24	7/30/24	
5	Fire Extinguishers and Cabinet Location Clarification	7/23/24	8/15/24	
6	Structural Finishes	7/30/24	8/02/24	
7	Glass Clarification	7/30/24	7/31/24	
8	Mechanical Clarifications - Additional	7/30/24	8/04/24	09/11/24
9	Steel Detail Clarifications	7/30/24	8/02/24	
10	Roof Equipment Screen Details	7/31/24	8/02/24	
11	Additional Mechanical Clarifications	8/02/24	8/15/24	
12	IT and AV room risers	8/7/24	8/15/24	
13	R-value of insulation above hard ceilings	8/12/24	8/15/24	
14	Glass Specification	8/13/24	8/15/24	
15	Acoustical Gypsum Ceiling Type CL-5	8/15/24	8/20/24	
16	Window Covering Clarifications	8/17/24	2/28/24	
	(END OF PRE-BID RFI'S)			

**OTHER DOCUMENTS**

<u>Reference</u>	<u>Description</u>	<u># Pages</u>	<u>Date</u>	<u>Revised</u>
	<b>Geotechnical Report(s)</b>			
	Report of Geotechnical Investigation	50	11/22/23	
	<b>Asbestos Survey(s)</b>			
	(END OF OTHER DOCUMENTS)			

**BID PACKAGES AND BID PACKAGE ADDENDA**

<b><u>BP No.</u></b>	<b><u>Bid Package Description</u></b>
1.02	Material Testing
1.13	Surveying
1.15	Final Cleaning
3.01	Concrete & Masonry
5.01	Structural & Miscellaneous Steel
6.02	Millwork & Casework
7.02	Sealants & Waterproofing
7.04	Architectural Metal Panels
7.06	Roofing
8.01	HM Frames / Doors / Hardware
8.03	Glass & Glazing
8.04	Overhead Doors
9.01	Metal Framing, Drywall & Stucco
9.03	Acoustical Ceilings & Wall Panels
9.04	Flooring – Hard Tile, Resilient Flooring, Base & Carpet
9.08	Access Flooring
9.09	Painting
10.01	Misc. Accessories
10.04	Signage
10.19	Protective Covers & Roof Screens
11.02	Loading Dock Equipment
11.03	Residential Equipment
12.01	Window Treatments
14.01	Elevators
21.01	Fire Sprinkler Systems
22.01	Plumbing Systems
23.01	Mechanical Systems
23.01	HVAC Test & Balance

<b>BP No.</b>	<b><u>Bid Package Description</u></b>
26.01	Electrical & Low Voltage Systems
31.01	Sitework & Utilities & Pavers
32.03	Landscaping / Irrigation

**END OF DOCUMENT LIST**

## **CLARIFICATIONS, QUALIFICATIONS AND ASSUMPTIONS**

### Basis of the GMP Proposal

- This GMP Proposal has been prepared based on the following documents:
  - The Contract Drawings entitled “Clearwater City Hall – Permit Set” dated July 05, 2024 as prepared by Wannemacher Jensen Architects, Inc and Consultants. Refer to Document List included in Section II of this proposal.
  - The Project Specifications entitled “Clearwater City Hall – Permit Set” dated July 05, 2024 as prepared by Wannemacher Jensen Architects, Inc and Consultants. Refer to Document List included in Section II of this proposal.
  - Addendum No. 1 prepared by Wannemacher Jensen Architects, Inc and their consultants, dated August 02, 2024, to the extent that the addendum was made available and issued to bidders by Ajax Building Company, LLC as part of a bid package addenda prior to their bid date.
  - Addendum No. 2 prepared by Wannemacher Jensen Architects, Inc and their consultants, dated August 23, 2024, to the extent that the addendum was made available and issued to bidders by Ajax Building Company, LLC as part of a bid package addenda prior to their bid date. NOTE THAT ADDENDUM NO. 2 IS CARREID AS AN ALLOWANCE WITHIN THE GMP PROPOSAL.
  - Pre-Bid Requests for Information (Pre-Bid RFI's) No. 01 - 16 to the extent that the information was made available and issued to bidders by Ajax Building Company, LLC as part of a bid package addendum prior to their bid date, with answers and/or clarifications provided by the Owner, the Architect and their consultants, or the Construction Manager.
  - The Construction Manager's GMP Cost Report dated September 24, 2024.
  - The Construction Manager's Project Schedule dated September 16, 2024.
  - The Bid Packages and Bid Package Addenda issued to bidders by the Construction Manager.
- It is understood that this GMP Proposal will require reconciliation, either additive or deductive, for scope increased or decreased between this GMP Proposal and the 100% Construction Documents.
- It is understood that various allowances are included in this GMP Proposal as indicated in Section IV-E of this proposal. It is further understood that the Construction Manager's Contract will require adjustments by change order (either additive or deductive) for reconciling the difference between each allowance and the actual costs and/or savings realized on each allowance. All allowances are to be utilized in accordance with Section 3.8.4 of the of the executed Agreement. All allowance expenditures must be approved in writing by the City of Clearwater.
- These qualifications, clarifications and assumptions are intended to supplement the GMP Cost Report and the GMP Documents, and are intended to inform the Owner and the Design Team of the Construction Manager's interpretation of the scope items which are included or excluded, and which may not be clearly shown or defined by specification, plan, elevation, detail, section, schedule, or schematic.

### Scope of the GMP Proposal

- The scope of this GMP Proposal consists of the following:
  - The Construction Manager's general conditions and general requirements for a period of twenty-two (22) months.
  - Base Bid GMP – Includes the following scope of work:
    - The project consists of the construction of a new two-story City Hall on an approximately 1.68-acre site in downtown Clearwater. The two-story building is approximately 40,303 square feet modern facility to accommodate multiple City departments including the City Council, City Manager and City Attorney.

The building will also house the new City Council Chambers. The building structure will be a composite steel system, metal framed exterior walls, cast-in-place shear walls and elevator shafts, and a metal panel exterior skin. The site development includes all hardscape including pervious concrete paving, park elements, storm draining to water gardens (ponds), and all associate MEP site elements.

- Alternates – The following “Alternates” have been priced and are offered for consideration as part of this proposal. Refer to Section IV-F of this proposal for a more detailed description and pricing for the alternates.
  - Alternate No. 1 – PV Panels & Sacrificial Roof at Solar Array

#### Division 01 – General Requirements

- Clarifications, qualifications and assumptions related to Division 01:
  - This GMP Proposal includes the Construction Manager’s general conditions and general requirements for a period of twenty-two (22) months.
  - The General Conditions in the amount of \$1,898,167 and General Requirements in the amount of \$589,566 are considered lump sum per Agreement between Owner and Construction Manager.
  - We have included the necessary jobsite supervision, layout, safety supplies, equipment, temporary jobsite office facility, postage, office equipment, project internet, and jobsite communications.
  - We have not included a jobsite office facility for the Owner, Architect, Engineer, or their representatives.
  - Aerial photographs have been included.
  - Building permits are not included as they are assumed to be paid directly by the Owner.
  - Environmental permits are not included.
  - Tap fees, connection charges, system charges, impact fees, meter fees, or other regulatory requirements/fees are not included as all utilities are being tied into existing utility services.
  - Costs related to a threshold inspector are not included.
  - Material testing is included.
  - Temporary utility services (water, sewer and electric) are included. It is assumed that all temporary utilities required for the project will be tied into permanent utilities and that these permanent utilities are readily accessible, of adequate size to handle any additional load as required by temporary utilities and that temporary on-site facilities can be located as necessary to prevent the need for any substantial overhead and/or underground temporary utilities.
  - The consumption costs associated with temporary water, sewer and electric utilities will be paid for by the Construction Manager through the date of Substantial Completion at which time these utilities shall be transferred into the Owner’s name and become the responsibility of the Owner.
  - We have included costs for Scheduling Software, Updates, Maintenance, and Support within the GMP as part of our lump sum General Conditions and General Requirements costs
  - We have included costs for MIS Services related to the project. This includes software updates associated with Ajax Building Company, LLC standard software provided for cost management, computer operating systems, PDF software, word processing applications, and spreadsheet applications. This includes troubleshooting, virus management/remediation, malware/adware management/remediation, updates, and maintenance of these systems. This does not include services related to scheduling, document control, and Project Management Controls, which are provided via other applications noted below. This does not include service provider costs for internet/telephone, initial setup, wiring, or connections. This cost is included as part of our lump sum General Conditions and General Requirements cost.
  - We have included costs for Document Management and Project Management Controls Services. These services will be provided via a cloud-based platform that will allow direct access to all Construction personnel, including Owners, Architects, and Subcontractors. Services will include the ability to access/manage the information via mobile devices via the internet. Services included will be Plans and

Specs Maintenance and distribution, RFI Control, Submittal Control, Punch List Management, Daily Reports, along with other related functions inherent in the platform. This cost is included as part of our lump sum General Conditions and General Requirements cost.

- We have included costs to host project-related video conferencing and file sharing. These services will be provided via cloud-based platforms. This cost is included as part of our lump sum General Conditions and General Requirements cost.
- We have included costs for Oracle Textura Payment Management (TPM) System for the administration of the subcontractor payment application process. This cost is included as part of our lump sum General Conditions and General Requirements cost.
- Temporary gravel, limerock, crushed concrete or asphalt millings is included for the stabilization of the construction entrances.
- Temporary jobsite fencing and gates are included as 6'-0" high chain link fencing.
- Silt fencing is included for areas where construction runoff and/or erosion may occur.
- We have included re-seeding areas disturbed by construction activities with seed as necessary to return those areas to their pre-construction condition. It should be understood that there will be a "growing in" period following the seeding operations.
- One (1) each standard 4' x 8' project sign is included.
- An existing condition survey is not included.
- The final project cleaning is included.
- Jobsite cleanup, rubbish removal and rubbish disposal are included.
- Surveying for building layout and elevation control is included.
- An as-built survey is included for the final documentation of the location and elevation of the proposed new construction.
- Performance and Payment Bonds are included.
- Labor burden multiplier is included as a fixed rate of 46%. This multiplier is to account for all added expenses related to direct labor that are not included as part of OH&P.
- We exclude any local, state, or federal prevailing wage acts or laws that mandate worker classification, prevailing wage rates, or fringe benefits, including the Davis-Bacon Act and other similar acts or laws.
- We have included this project's portion of our Umbrella / General Liability Insurance Policy within the GMP. The charge for this coverage shall be \$310,740 and shall be billed as a lump sum amount upon approval of the GMP and issuance of the Notice to Proceed.
- The Builder's Risk Insurance Policy shall be provided by the Owner. The policy shall list Ajax Building Company, LLC and their subcontractors as additional insureds and the Owner shall provide for a waiver of subrogation with Ajax Building Company, LLC and their subcontractors.
- We have included Warranty Management for the project within the GMP. The charge for this service to be provided during the warranty period shall be \$11,838 and shall be billed as a lump sum amount upon project Substantial Completion.
- A Construction Manager's Contingency is included. This contingency is to be utilized by Ajax Building Company, LLC in executing the work described in this GMP Proposal as identified in the Agreement Between Owner and Construction Manager.
- Based on current market volatility, a Pre-Purchase Refinement Allowance of \$200,000 is included. The purpose of this allowance is to reconcile the buyout after GMP award for costs associated with supply chain impacts subsequent to the buyout reconciliation change order.
- Architectural and/or Engineering Fees are not included.
- The Construction Manager's Construction Phase Fee is included at the rate of 3.85% of the GMP which shall be converted to a lump sum upon acceptance of the GMP.
- This GMP Proposal includes estimating services for the reconciliation of the GMP between the GMP Documents (refer to Section II of this proposal) and the 100% Construction Documents scheduled to be

issued by the Architect on October 02, 2024. Preconstruction or estimating services beyond this GMP reconciliation are not included.

- This proposal does not include any provisions for enhanced hurricane protection (EHPA).
- We exclude any local, state, or federal prevailing wage acts or laws that mandate worker classification, prevailing wage rates, or fringe benefits, including the Davis-Bacon Act and other similar acts or laws.
- Should the Owner elect to utilize the Direct Purchase Order process to save sales tax, the tax for actual purchases will be credited to the Owner. At the end of the Project, any refund for materials not purchased or surplus materials returned to suppliers plus the applicable sales tax amount shall be credited with an additive Change Order to the Agreement with the Construction Manager and Subcontractor's Agreement. Surplus materials shall be the property of the Subcontractor and no refund or materials shall be due to the Owner.
- Appendix A to the project specifications is excluded from this GMP Proposal. General Conditions and Contract Documents are as negotiated in the executed Agreement Between Owner and Construction Manager. Any technical specifications required for this project are to be incorporated into the Project Specifications.
- As Addendum No. 2 was issued late in the GMP development process, we have included an Allowance of \$350,000 to cover the potential cost of these changes.
- As the final Permit Comments from the City have not fully been received nor has the Architect provide updated responses for such, we have included an Allowance of \$100,000 for potential costs associated with permitting comments.
- An Owner Move Assist Allowance of \$20,000 is included.
- A Temporary Protection Measures Allowance of \$25,000 is included to address potential protections needed due to storm events.
- Included an Allowance of \$40,000 for additional construction related work that may be required to support the Owner provide Public Art for the new building.
- We acknowledge the City of Clearwater is seeking LEED Silver Certification for this project and have included administration as required by the Contract Documents for this effort.
- We have reduced the general conditions and general requirements in the amount of \$54,229 in anticipation that the MSB portion of the project will be concurrent with City Hall. Should this not occur, an adjustment to the City Hall General Conditions and General Requirements will be required via change order.

#### Division 02 – Existing Conditions

- Clarifications, qualifications and assumptions related to Division 02:
  - Abatement and Remediation Work
    - We specifically exclude any asbestos abatement, lead paint abatement or removal, PCB abatement or removal, and related surveys, air monitoring, clearances, testing services, etc.
  - Demolition / Selective Demolition
    - Demolition work and selective demolition work, as required for new construction, is included in this proposal.
    - The water and runoff generated from construction operations will be contained on the project site. It is assumed that the water and/or runoff generated from demolition operations will not require collection, treatment or disposal.
    - It is assumed that abandoned utilities will be disconnected and capped (not removed or filled), unless specifically denoted otherwise on the Contract Documents.
    - We specifically exclude the relocation and/or reinstallation of any existing or temporary buildings, structures, etc.



Division 03 – Concrete

- Clarifications, qualifications and assumptions related to Division 03:
  - Concrete Work
    - Standard subsoil termite treatment is included at the slab sub-grade. No special or extended warranties are included.
  - General Concrete Items
    - No colored concrete, special mixes, special finishes, or admixtures are included.
    - We exclude any special rebar finishes, galvanizing, epoxy coatings, or special chairs/supports.

Division 04 – Masonry

- Clarifications, qualifications and assumptions related to Division 04:
  - Masonry Work
    - All cmu masonry is included as standard cmu. Fire rated, ground face, fluted, acoustical, colored or other special cmu are not included.
    - Special cmu admixtures are not included.
    - Bonds for all cmu and brick masonry are included as standard running bond.
    - All masonry grout is included as standard weight, 3000 psi, regular grout, with no color, strength or other additives (7-9 inch slump).
  - General Masonry Items
    - Mortar additives or coloring are not included.
    - Exposed masonry joints are included as concave joints both horizontally and vertically.

Division 05 – Metals

- Clarifications, qualifications and assumptions related to Division 05:
  - Structural Steel, Joists and Deck
    - All architecturally exposed interior exposed structural steel will be AESS 3 preparation.
    - All architecturally exposed exterior steel, such as at curved columns will be AESS 4 preparation.
    - Miscellaneous framing and supports as indicated on the drawings will be hot-dipped galvanized and level of finish for exposed to view noted above.
    - Touch up painting for shop painted surfaces will be 2.0-mil dry film thickness.
  - Miscellaneous and Fabricated Metals
    - Exterior Stair Railings and interior Lobby Stair railings are included as Aluminum finish.
  - Cold-Formed Metal Framing
    - Includes delegated engineering.

Division 06 – Wood, Plastics and Composites

- Clarifications, qualifications and assumptions related to Division 06:
  - Finish Carpentry
    - Includes the WD2-Slat Wall.
  - Architectural Woodwork
    - Included an Allowance of \$50,000 for ballistic assembly @ Dais, as this has been discussed but not reflected on the GMP documents.

Division 07 – Thermal and Moisture Protection

- Clarifications, qualifications and assumptions related to Division 07:
  - Waterproofing
    - Includes both exterior elevator pit waterproofing and interior of pit waterproofing.
    - We have included a peel-and-stick waterproofing membrane behind metal wall panel assembly as the specified fluid applied air/moisture barrier does not work well with fastener penetrations. Will submit product data for review and approval.
  - Spray Applied Fireproofing
    - Excludes fireproofing as none specified or shown.
  - Metal Panels
    - Included basis of design as specified.
    - Due to late discussions with the basis of design panel provider regarding pricing elements, it is still under review as to accessories and installation requirements for a complete system installation. As such, we have included an Allowance of \$125,000 for further panel engineering and coordination.
  - Roofing and Sheet Metal
    - Included as specified; however, see Alternate No. 1 for Sacrificial Roof for Solar Array.
  - Joint Sealers
    - Include in Water Proofing Bid Package.

Division 08 – Openings

- Clarifications, qualifications and assumptions related to Division 08:
  - Metal Doors and Frames
    - All hollow metal frames are included as standard hollow metal. No mastic painting, asphalt painting, or back priming is included for hollow metal frames.
    - No zinc-rich priming is included.
    - Frameless door to be ISD-Ezy Jamb Inswing Door Frame with SOSS Hinges.
  - Wood Doors
    - White Birch wood doors with factory finish is included.
  - Specialty Doors
    - Included Cookson, model ESD10 Non-insulated rolling steel door with standard colors (white, brown grey or tan).
    - ½ HP operator with auxiliary chain hoist
    - Padlockable slide locks
    - Electric sensing edge
  - Entrances and Storefronts
    - Aluminum Exterior Storefront
      - Included as Kawneer 1R501T 2-3/4" x 5"
      - Finish: 2-coat Custom Paint – Color TBD
      - Glazing: Viracon 1-5/16" VUE1-50 Insulating Laminate Glass FT/HS/HS
    - Aluminum Exterior Entrance Doors
      - Included as Kawneer 5000IR Wide Stile Doors
      - Glass: 1 1/16" VUE1-50 Insulating Laminated Glass FT/HS/HS
    - Aluminum Interior Storefront
      - Included as Kawneer TriFab 451 Versa Glaze 2" x 4-1/2"
      - Finish: 2-coat Custom Paint – Color TBD
      - Glazing: 9/16" Clear Laminated

- Glazing to include privacy vinyl film as indicated, not fritted glazing
- Aluminum Interior Entrance Doors
  - Included as Kawneer 500 Wide Stile
  - Glass: 9/16" Clear Laminated
  - Glass to include privacy vinyl film as indicated, not fritted glass
- Bird friendly glass has been excluded as reference to it was removed in Addendum 1.
- Finished Hardware
  - Included as specified
  - Dual door operators, push plates, safety sensors and bollards are provided as Assa Abloy at door marks 100A, 100B, 100C and 100D.
- Curtain Wall
  - Included as Kawneer 1600IR-SYS 1 2-1/2" x 7 -13/16"
  - Finish: 2-cost Custom Paint – Color TBD
  - Glazing: Viracon 1-5/16" VUE1-50 Insulating laminate Glass FT/HS/HS

#### Division 09 – Finishes

- Clarifications, qualifications and assumptions related to Division 09:
  - Gypsum Board, Plaster and Stucco Systems
    - Included Level 5 finish drywall.
    - Included end wall mullion caps at intersection of drywall to Storefront / Curtainwall assemblies.
    - No interior veneer plaster or hard coat finishes are included.
    - Abuse resistant gypsum board is not included unless clearly identified on the Contract Drawings.
    - Mold/mildew resistant gypsum board is not included unless clearly identified on the Contract Drawings.
  - Tile Work
    - No special tile patterns, mosaics, colors or shapes are included.
  - Access flooring
    - Included "TATE" ConCore 1250 grade panel or similar with bolted stringer to accommodate a 12" raised floor height.
  - Finished Flooring
    - Resilient Flooring
      - Included as specified. Included Static dissipative tile at access floor location
  - Acoustical Treatment
    - Acoustical ceilings
      - All acoustical ceilings are included as standard 9/16" exposed grid with tegular 24"x24"x5/8" or 30"x30"x5/8" ceiling tiles. No special acoustical grid systems, tiles, tile colors, tile patterns, special tile edges, tegular, etc. have been included other than what has been mentioned above.
      - Included as specified.
    - Acoustical wall panels
      - AWP-1 and AWP-2
      - FP-1 FlizFely Crossing Hanging Panel, standard sized room dividers (non-stacking three channel track)
      - FP-2 FlizFelt Rain wall panel install with Z-clips
  - Paints and Coatings
    - Included Dryfall or similar at exposed metal joist/deck
    - Concrete sealer at smooth finished concrete floors
    - No painting is included for concealed areas or areas otherwise not exposed to view.

Division 10 – Specialties

- Clarifications, qualifications and assumptions related to Division 10:
  - Miscellaneous Building Specialties
    - Included as specified, of note:
      - Toilet Partitions
      - Toilet Accessories
      - Electric Hand Dryers
      - Fire Extinguishers & Cabinets
      - Bike Racks & Bick Repair Station
      - Site Furnishing – Benches and Trash Cans
      - Flag Poles – (3)
      - Stainless Steel Corner Guards
      - Visual Display Boards
      - Knox Box
  - Signage and Plaques
    - Included an Allowance of \$42,829 for interior and exterior signage.
  - Walkway Covers and Exterior Protective Construction
    - Included exterior covers at the two stair locations.
    - Included the Louvered Screens at RTU location at Roof level.

Division 11 – Equipment

- Clarifications, qualifications and assumptions related to Division 11:
  - Residential Appliances
    - (4) Stainless Dishwashers
    - (4) Countertop Microwaves
    - (4) Side by Side Refrigerators
    - (1) Undercounter refrigerator
    - Items above are included as an allowance of \$30,000 and is based on similar models to what has been listed in the construction documents. Some of the listed items are no longer in production so similar models have been included.

Division 12 – Furnishings

- Clarifications, qualifications and assumptions related to Division 12:
  - Furnishings and Accessories
    - Includes an allowance of \$750,000 for Furniture / Furnishings and Equipment.
  - Window Treatment
    - A mechoshade product has been included as specified.

Division 14 – Conveying Systems

- Clarifications, qualifications and assumptions related to Division 14:
  - Elevators
    - Included TKE Elevators as specified.

Division 21 – Fire Suppression

- Clarifications, qualifications and assumptions related to Division 21:
  - Fire Protection Systems
    - The Architect/Engineer of Record shall provide all required fire protection system engineering documents for the project, including all engineering, calculations, analysis, and other data required to set forth the overall design requirements and provide sufficient direction to the construction manager for the layout and construction of the fire protection system(s) and shall be signed and sealed by the Engineer of Record and meet all requirements of the authority having jurisdiction. The construction manager's fire protection subcontractor shall provide all required fire protection system layout documents for the project, including layout, sizing, hydraulic calculations and other construction data that shall provide the requirements for the fabrication and installation of the fire protection system(s) and shall prepare and submit for review/approval, shop drawings and product data for the fire protection system(s) based upon the design documents provided by the Architect/Engineer of Record. Shop drawings and product data shall not require any additional engineering input, and shall not be required to be signed/sealed by a delegated engineer.

Division 22 – Plumbing

- Clarifications, qualifications and assumptions related to Division 22:
  - Plumbing Work
    - Includes code minimum pipe sizes lacking on the plans for the group restrooms on first and second floor.
    - Includes the increased correct water line sizes for fixtures that are incorrectly shown on the isometric and plan sheets.
    - Domestic water pump included.
    - Includes hammer arrestors not shown but required by code.

Division 23 – HVAC

- Clarifications, qualifications and assumptions related to Division 23:
  - HVAC Work
    - Trane Controls are included.
    - Includes the receipt, installation and warranty for Owner Direct purchased Chillers and RTU's.
    - Testing, Adjusting and Balancing
    - Commissioning is excluded. If required will be performed by others.

Division 26 – Electrical, Division 27 Communications and Division 28 Electronic Safety & Security

- Clarifications, qualifications and assumptions related to Division 26:
  - Included an Allowance of \$250,000 for the Unlist Focal Point Acoustical Baffles
  - Includes the EV Charging stations as shown on the Site Plans
  - Includes the receipt, installation and warranty for Owner Direct purchased Generator and Switch Gear.
  - Includes the electrical rough-in as shown on documents for the future Photo Voltaic (PV) installation. See Alternate No. 1 for addition of roof PV Panels.
  - Basic Materials and Methods

- Secondary electrical service from the primary transformer to the building(s) and electrical service distribution thereafter is included. The Construction Manager assumes that the Owner's local utility company will install the primary electrical service from the utility company's infrastructure to the on-site transformer, including furnishing and installing the primary transformer and related housekeeping pad.
- Jacking, boring, or directional drilling is not included for new or relocated utilities.
- Includes all systems as denoted by Contractor on the Responsibility Matrix on Drawing T-000.Identification. Following systems are denoted as Owner provided and installed by others. We have included the specified conduit, pullstrings and rough-in only for these systems:
  - Access Control
  - Fire Alarm
  - Security System & Cameras
  - CCTV
- Includes Time Clocks as specified.
- Distributed Antenna Systems (DAS) is included as specified.

#### Division 31 – Earthwork

- Clarifications, qualifications and assumptions related to Division 31:
  - Site Work / Earthwork
    - It is assumed that the existing soils are of an acceptable material and that compaction can be achieved under normal means and methods, and that over-excavation and/or replacement of unsuitable soils will not be required in the performance of the work.
    - Based on Geotechnical Report provide it is not anticipated that mass dewatering will be required, as such, mass dewatering is excluded.
    - Included an Allowance of \$60,000 for relocating on site potential unsuitable soil.

#### Division 32 – Exterior Improvements

- Clarifications, qualifications and assumptions related to Division 32:
  - Paving
    - We have not included any milling and/or resurfacing of existing roadways, parking lots or drives. It is anticipated that various roadways, paving, parking lots, etc. surrounding the project site will require resurfacing and/or repair at the completion of the project. We recommend that a more detailed evaluation be performed by the project team during the later stages of the project so that a definitive scope of work can be prepared and priced accordingly.

#### Division 33 – Utilities

- Clarifications, qualifications and assumptions related to Division 33:

#### General Notes

- General clarifications, qualifications and assumptions related to the GMP Proposal:
  - In order to maintain the project schedule, the installation and/or finishing of drywall, cabinets, casework, and other similar finishes/components may be required to commence prior to the HVAC system(s) being operational, conditioned air being achieved, and/or the final perimeter building envelope being fully enclosed. It is anticipated that the building will be substantially dry prior to the installation of these elements.

- Electronic, CAD or BIM “As-Built” are not included. Ajax Building Company, LLC will maintain “As-Built” drawings at the jobsite throughout the construction phase and provide copies to the Architect and Owner at Final Completion.
- O&M training, manuals or video-training is not included for Owner furnished equipment or items provided by the Owner’s vendors.
- This GMP Proposal is not a line item GMP. Reallocation of any funds and/or budgets within the GMP (excluding allowances and General Conditions/General Requirements) is allowed with Owner concurrence, which shall not be unreasonably withheld.
- Various unforeseen conditions and discrepancies may arise during the construction phase. It is assumed that the Design Team and Owner will assign a staff member(s) that will be readily available to respond and provide timely assistance in resolving all issues that may arise.

**END OF CLARIFICATIONS, QUALIFICATIONS AND ASSUMPTIONS TO THE GMP PROPOSAL**

## **COST REPORT NARRATIVE**

Ajax Building Company, LLC is confident that the GMP Cost Report included herein is representative of the proposed scope of work depicted in the GMP Documents. The work included in the GMP Proposal is based upon the List of Documents included in Section II of this proposal as amended by 1) the Clarifications, Qualifications, and Assumptions and 2) the Allowance Schedule, contained in Sections III and IV of this proposal.

The Base Bid GMP Proposal for the Clearwater City Hall totals **\$29,605,458**. The Base Bid GMP Proposal includes the construction of a new two-story City Hall on an approximately 1.68-acre site in downtown Clearwater. The two-story building is approximately 40,303 square feet modern facility to accommodate multiple City departments including the City Council, City Manager and City Attorney. The building will also house the new City Council Chambers. The building structure will be a composite steel system, metal framed exterior walls, cast-in-place shear walls and elevator shafts, and a metal panel exterior skin. The site development includes all hardscape including pervious concrete paving, park elements, storm draining to water gardens (ponds), and all associate MEP site elements.

This GMP Proposal No. 2 Final cumulative total is **\$29,605,458**. Upon acceptance, the cumulative Contract Sum will be \$29,605,458, inclusive of this GMP Proposal, previously accepted GMP Proposals, and Contract Amendments to date. The increase for the GMP Amendment 2 is calculated as follows:

- |                                     |                      |
|-------------------------------------|----------------------|
| • GMP 2 Final cumulative total      | \$29,605,458         |
| • GMP 1 ERP total / Amendment No. 1 | <u>(\$7,407,439)</u> |
| • Amendment No. 2 Total             | <b>\$22,198,019</b>  |

The Construction Manager's Preconstruction Phase Services is not included in the GMP No. 1 – Early Release Package. Per Contract, the CM Preconstruction Phase Services total \$369,965. This Preconstruction Phase fee included \$269,360 allocated to the City Hall project (22-0019-EN) and the remaining \$100,605 to the MSB Renovation project (23-0035-EN).

In addition to the Base Bid GMP Proposal, Ajax Building Company, LLC has provided pricing for "Alternates" for consideration by City of Clearwater, included in Sections IV-E respectively.



GMP Cost Report:

**BASE BID GMP**  
CM Summary Report

# Cost Management Recap



Sort Sequences:

1. Sec
2. Major Item Code
3. Not Used
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.es

Estimator:

Primary Project Qty:0 \$

Secondary Project Qty: 0 FLF

Estimate UM: Imperi

**Report includes Taxes & Insurance.**

2:59:21PM

9/24/2024

Description	Unit\$	Total \$
<b><u>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!</u></b>		
<b>Total Major Item Code 01300.000</b>		<b>\$1,898,167</b>
<b>GENERAL CONDITIONS</b>		
<b>Total Major Item Code 01300.300</b>		<b>\$589,566</b>
<b>GENERAL REQUIREMENTS</b>		
<b>Total Major Item Code 02000.000</b>		<b>\$114,780</b>
<b>MISCELLANEOUS ITEMS</b>		
<b>Total Major Item Code 03000.000</b>		<b>\$2,181,348</b>
<b>CONCRETE WORK</b>		
<b>Total Major Item Code 05000.000</b>		<b>\$2,744,554</b>
<b>STRUCTURAL STEEL, JOISTS, &amp; DECK</b>		
<b>Total Major Item Code 06400.000</b>		<b>\$485,812</b>
<b>ARCHITECTURAL WOODWORK</b>		
<b>Total Major Item Code 07100.000</b>		<b>\$80,022</b>
<b>WATERPROOFING &amp; DAMPPROOFING</b>		
<b>Total Major Item Code 07400.000 ROOFING</b>		<b>\$788,547</b>
<b>&amp; SIDING PANELS</b>		
<b>Total Major Item Code 07500.000 ROOFING</b>		<b>\$587,385</b>
<b>&amp; SHEET METAL</b>		
<b>Total Major Item Code 08000.000 BASIC</b>		<b>\$185,852</b>
<b>DOOR &amp; WINDOW MATERIALS &amp;</b>		
<b>METHODS</b>		
<b>Total Major Item Code 08300.000</b>		<b>\$18,350</b>
<b>SPECIALTY DOORS</b>		
<b>Total Major Item Code 08400.000</b>		<b>\$2,056,720</b>
<b>ENTRANCES &amp; STOREFRONTS</b>		
<b>Total Major Item Code 09100.000 GYP</b>		<b>\$2,309,633</b>
<b>BOARD, PLASTER, &amp; STUCCO SYSTEMS</b>		
<b>Total Major Item Code 09500.000 CEILINGS</b>		<b>\$341,369</b>
<b>Total Major Item Code 09600.000 FINISHED</b>		<b>\$659,080</b>
<b>FLOORING</b>		
<b>Total Major Item Code 09900.000 PAINTS &amp;</b>		<b>\$181,712</b>
<b>COATINGS</b>		
<b>Total Major Item Code 10000.000</b>		<b>\$475,338</b>
<b>MISCELLANEOUS BUILDING SPECIALTIES</b>		
<b>Total Major Item Code 11000.000 BUILDING</b>		<b>\$61,683</b>
<b>EQUIPMENT</b>		
<b>Total Major Item Code 12000.000 BUILDING</b>		<b>\$855,000</b>
<b>FURNISHINGS</b>		
<b>Total Major Item Code 14000.000</b>		<b>\$393,355</b>
<b>CONVEYING SYSTEMS</b>		

Sort Sequences:

1. Sec
2. Major Item Code
3. Not Used
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.es

Estimator:

Primary Project Qty:0 \$

Secondary Project Qty: 0 FLF

Estimate UM: Imperi

Report includes Taxes &amp; Insurance.

2:59:21PM

9/24/2024

Description	Unit\$	Total \$
<b><u>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!</u></b>		
<b>Total Major Item Code 21000.000 FIRE SUPPRESSION SYSTEMS</b>		<b>\$221,304</b>
<b>Total Major Item Code 22000.000 PLUMBING WORK</b>		<b>\$932,990</b>
<b>Total Major Item Code 23000.000 HEATING, VENTILATION, &amp; AIR CONDITIONING</b>		<b>\$2,378,094</b>
<b>Total Major Item Code 26000.000 ELECTRICAL WORK</b>		<b>\$3,983,537</b>
<b>Total Major Item Code 27000.000 COMMUNICATIONS SYSTEMS</b>		
<b>Total Major Item Code 31000.000 SITEWORK</b>		<b>\$1,430,356</b>
<b>Total Major Item Code 32000.000 SITE IMPROVEMENTS</b>		<b>\$263,462</b>
<b>Total Major Item Code 35000.000 ALLOWANCES</b>		<b>\$535,000</b>
<b>Total Major Item Code 36000.000 BONDS &amp; INSURANCE</b>		<b>\$526,778</b>
<b>Total Major Item Code 37000.000 WARRANTIES</b>		<b>\$11,838</b>
<b>Total Major Item Code 50000.000 ESCALATION COSTS</b>		<b>\$200,000</b>
<b>Total Major Item Code 80000.000 CONTINGENCY</b>		<b>\$1,035,801</b>
<b>Total Major Item Code 95000.000 OVERHEAD &amp; FEES</b>		<b>\$1,078,025</b>
<b>Total Sec BB BASE BID</b>		<b>\$29,605,458</b>

GMP Cost Report:

**BASE BID GMP**  
CM Detail Report

# Cost Management Detail



Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF

Secondary Project Qty: 0 FLRS

Estimate UM: Imperial

**Report includes Taxes & Insurance.**

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			
<b>Sec BB BASE BID</b>			
<b>Major Item Code 01300.000 GENERAL CONDITIONS</b>			
<b>Minor Item Code 01300.000 ADMINISTRATIVE REQUIREMENTS</b>			
General Conditions	1.00 LS	1,898,167.00	1,898,167
<b>Total Minor Item Code 01300.000 ADMINISTRATIVE REQUIREMENTS</b>			<b>\$1,898,167</b>
<b>Total Major Item Code 01300.000 GENERAL CONDITIONS</b>			<b>\$1,898,167</b>
<b>Major Item Code 01300.300 GENERAL REQUIREMENTS</b>			
<b>Minor Item Code 01300.000 ADMINISTRATIVE REQUIREMENTS</b>			
General Requirements	1.00 LS	589,566.00	589,566
<b>Total Minor Item Code 01300.000 ADMINISTRATIVE REQUIREMENTS</b>			<b>\$589,566</b>
<b>Total Major Item Code 01300.300 GENERAL REQUIREMENTS</b>			<b>\$589,566</b>
<b>Major Item Code 02000.000 MISCELLANEOUS ITEMS</b>			
<b>Minor Item Code 02000.000 MISCELLANEOUS ITEMS</b>			
Temporary Fence & Windscreen	1.00 LS	29,000.00	29,000
BP 01.02 Laboratory Testing	1.00 LS	36,080.00	36,080
BP 01.13 Surveying	1.00 LS	35,000.00	35,000
BP 01.15 Final Cleaning	1.00 LS	14,700.00	14,700
<b>Total Minor Item Code 02000.000 MISCELLANEOUS ITEMS</b>			<b>\$114,780</b>
<b>Total Major Item Code 02000.000 MISCELLANEOUS ITEMS</b>			<b>\$114,780</b>
<b>Major Item Code 03000.000 CONCRETE WORK</b>			
<b>Minor Item Code 03300.000 CAST-IN-PLACE CONCRETE</b>			
BP 03.01 Concrete	1.00 LS	2,181,348.00	2,181,348
<b>Total Minor Item Code 03300.000 CAST-IN-PLACE CONCRETE</b>			<b>\$2,181,348</b>
<b>Total Major Item Code 03000.000 CONCRETE WORK</b>			<b>\$2,181,348</b>
<b>Major Item Code 05000.000 STRUCTURAL STEEL, JOISTS, &amp; DECK</b>			
<b>Minor Item Code 05120.000 STRUCTURAL STEEL</b>			
BP 05.01 Structural Steel Misc Metals	1.00 LS	2,744,554.00	2,744,554
<b>Total Minor Item Code 05120.000 STRUCTURAL STEEL</b>			<b>\$2,744,554</b>

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF  
 Secondary Project Qty: 0 FLRS  
 Estimate UM: Imperial

Report includes Taxes &amp; Insurance.

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			
<b>Total Major Item Code 05000.000</b>			<b>\$2,744,554</b>
<b>STRUCTURAL STEEL, JOISTS, &amp; DECK</b>			
<b>Major Item Code 06400.000 ARCHITECTURAL WOODWORK</b>			
<b>Minor Item Code 06400.000 ARCHITECTURAL WOODWORK</b>			
BP 06.02 Millwork	1.00	LS	435,812.00
Ballistic Assembly @ Dais - Allowance	1.00	ALLW	50,000.00
<b>Total Minor Item Code 06400.000</b>			<b>\$485,812</b>
<b>ARCHITECTURAL WOODWORK</b>			
<b>Total Major Item Code 06400.000</b>			<b>\$485,812</b>
<b>ARCHITECTURAL WOODWORK</b>			
<b>Major Item Code 07100.000 WATERPROOFING &amp; DAMPPROOFING</b>			
<b>Minor Item Code 07100.000 WATERPROOFING &amp; DAMPPROOFING</b>			
BP 07.02 Sealants & Waterproofing	1.00	LS	80,022.00
<b>Total Minor Item Code 07100.000</b>			<b>\$80,022</b>
<b>WATERPROOFING &amp; DAMPPROOFING</b>			
<b>Total Major Item Code 07100.000</b>			<b>\$80,022</b>
<b>WATERPROOFING &amp; DAMPPROOFING</b>			
<b>Major Item Code 07400.000 ROOFING &amp; SIDING PANELS</b>			
<b>Minor Item Code 07410.000 METAL ROOF &amp; WALL PANELS</b>			
BP 07.04 Metal & Composite Panels	1.00	LS	663,547.00
Finalize Metal Panel Requirements Allowance	1.00	ALLW	125,000.00
<b>Total Minor Item Code 07410.000 METAL</b>			<b>\$788,547</b>
<b>ROOF &amp; WALL PANELS</b>			
<b>Total Major Item Code 07400.000 ROOFING &amp; SIDING PANELS</b>			<b>\$788,547</b>
<b>Major Item Code 07500.000 ROOFING &amp; SHEET METAL</b>			
<b>Minor Item Code 07500.000 MEMBRANE ROOFING</b>			
BP 07.06 Roofing	1.00	LS	587,385.00
<b>Total Minor Item Code 07500.000</b>			<b>\$587,385</b>
<b>MEMBRANE ROOFING</b>			
<b>Total Major Item Code 07500.000 ROOFING &amp; SHEET METAL</b>			<b>\$587,385</b>
<b>Major Item Code 08000.000 BASIC DOOR &amp; WINDOW MATERIALS &amp; METHODS</b>			
<b>Minor Item Code 08000.000 DOORS, FRAMES, &amp; HARDWARE</b>			
BP 08.01 Doors, Frames & Hardware	1.00	LS	185,852.00
<b>Total Minor Item Code 08000.000 DOORS, FRAMES, &amp; HARDWARE</b>			<b>\$185,852</b>
<b>BASIC DOOR &amp; WINDOW MATERIALS &amp; METHODS</b>			
<b>Total Major Item Code 08000.000 BASIC DOOR &amp; WINDOW MATERIALS &amp; METHODS</b>			<b>\$185,852</b>
<b>Major Item Code 08300.000 SPECIALTY DOORS</b>			
<b>Minor Item Code 08300.000 SPECIALTY DOORS</b>			
BP 08.04 Overhead Doors	1.00	LS	18,350.00
<b>Total Minor Item Code 08300.000</b>			<b>\$18,350</b>
<b>SPECIALTY DOORS</b>			
<b>Total Major Item Code 08300.000 SPECIALTY DOORS</b>			<b>\$18,350</b>
<b>Major Item Code 08400.000 ENTRANCES &amp; STOREFRONTS</b>			

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF  
 Secondary Project Qty: 0 FLRS  
 Estimate UM: Imperial

Report includes Taxes &amp; Insurance.

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			
<b>Minor Item Code 08400.000 ENTRANCES &amp; STOREFRONTS</b>			
BP 08.03 Entrances & Storefronts	1.00 LS	2,056,720.00	2,056,720
<b>Total Minor Item Code 08400.000</b>			<b>\$2,056,720</b>
<b>ENTRANCES &amp; STOREFRONTS</b>			
<b>Total Major Item Code 08400.000</b>			<b>\$2,056,720</b>
<b>ENTRANCES &amp; STOREFRONTS</b>			
<b>Major Item Code 09100.000 GYP BOARD, PLASTER, &amp; STUCCO SYSTEMS</b>			
<b>Minor Item Code 09250.000 GYPSUM BOARD</b>			
BP 09.01 Drywall & Stucco	1.00 LS	2,309,633.00	2,309,633
<b>Total Minor Item Code 09250.000</b>			<b>\$2,309,633</b>
<b>GYPSUM BOARD</b>			
<b>Total Major Item Code 09100.000 GYP</b>			<b>\$2,309,633</b>
<b>BOARD, PLASTER, &amp; STUCCO SYSTEMS</b>			
<b>Major Item Code 09500.000 CEILINGS</b>			
<b>Minor Item Code 09500.000 CEILINGS</b>			
BP 09.03 Acoustical Ceilings & Wall Panels	1.00 LS	341,369.00	341,369
<b>Total Minor Item Code 09500.000</b>			<b>\$341,369</b>
<b>CEILINGS</b>			
<b>Total Major Item Code 09500.000 CEILINGS</b>			<b>\$341,369</b>
<b>Major Item Code 09600.000 FINISHED FLOORING</b>			
<b>Minor Item Code 09600.000 FLOORS</b>			
BP 09.05 Flooring	1.00 LS	645,780.00	645,780
BP 09.08 Access Flooring	1.00 LS	13,300.00	13,300
<b>Total Minor Item Code 09600.000 FLOORS</b>			<b>\$659,080</b>
<b>Total Major Item Code 09600.000 FINISHED</b>			<b>\$659,080</b>
<b>FLOORING</b>			
<b>Major Item Code 09900.000 PAINTS &amp; COATINGS</b>			
<b>Minor Item Code 09900.000 PAINTS &amp; COATINGS</b>			
BP 09.09 Painting	1.00 LS	181,712.00	181,712
<b>Total Minor Item Code 09900.000 PAINTS</b>			<b>\$181,712</b>
<b>&amp; COATINGS</b>			
<b>Total Major Item Code 09900.000 PAINTS &amp;</b>			<b>\$181,712</b>
<b>COATINGS</b>			
<b>Major Item Code 10000.000 MISCELLANEOUS BUILDING SPECIALTIES</b>			
<b>Minor Item Code 10000.000 MISCELLANEOUS SPECIALTIES</b>			
BP 10.01 Miscellaneous Building Specialties	1.00 LS	147,597.00	147,597
BP 10.04 Signage	1.00 ALLW	57,896.00	57,896
BP 10.19 Protective Covers / Rooftop Screens	1.00 LS	269,845.00	269,845
<b>Total Minor Item Code 10000.000</b>			<b>\$475,338</b>
<b>MISCELLANEOUS SPECIALTIES</b>			
<b>Total Major Item Code 10000.000</b>			<b>\$475,338</b>
<b>MISCELLANEOUS BUILDING SPECIALTIES</b>			
<b>Major Item Code 11000.000 BUILDING EQUIPMENT</b>			
<b>Minor Item Code 11000.000 MISCELLANEOUS EQUIPMENT</b>			
BP 11.02 Loading Dock Equipment	1.00 LS	31,683.00	31,683
BP 11.03 Residential Equipment Allowance	1.00 ALLW	30,000.00	30,000

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF

Secondary Project Qty: 0 FLRS

Estimate UM: Imperial

Report includes Taxes &amp; Insurance.

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			
<b>Total Minor Item Code 11000.000 MISCELLANEOUS EQUIPMENT</b>			<b>\$61,683</b>
<b>Total Major Item Code 11000.000 BUILDING EQUIPMENT</b>			<b>\$61,683</b>
<b>Major Item Code 12000.000 BUILDING FURNISHINGS</b>			
<b>Minor Item Code 12000.000 MISCELLANEOUS FURNISHINGS</b>			
BP 12.01 Window Treatments	1.00 LS	105,000.00	105,000
BP 12.11 Furnishings / FFE	1.00 ALLW	750,000.00	750,000
<b>Total Minor Item Code 12000.000 MISCELLANEOUS FURNISHINGS</b>			<b>\$855,000</b>
<b>Total Major Item Code 12000.000 BUILDING FURNISHINGS</b>			<b>\$855,000</b>
<b>Major Item Code 14000.000 CONVEYING SYSTEMS</b>			
<b>Minor Item Code 14000.000 CONVEYING SYSTEMS</b>			
BP 14.01 Elevators	1.00 LS	393,355.00	393,355
<b>Total Minor Item Code 14000.000 CONVEYING SYSTEMS</b>			<b>\$393,355</b>
<b>Total Major Item Code 14000.000 CONVEYING SYSTEMS</b>			<b>\$393,355</b>
<b>Major Item Code 21000.000 FIRE SUPPRESSION SYSTEMS</b>			
<b>Minor Item Code 21005.000 COMMON WORK RESULTS - FIRE SUPPRESSION</b>			
BP 21.01 Fire Suppression	1.00 LS	221,304.00	221,304
<b>Total Minor Item Code 21005.000 COMMON WORK RESULTS - FIRE SUPPRESSION</b>			<b>\$221,304</b>
<b>Total Major Item Code 21000.000 FIRE SUPPRESSION SYSTEMS</b>			<b>\$221,304</b>
<b>Major Item Code 22000.000 PLUMBING WORK</b>			
<b>Minor Item Code 22010.000 COMMON WORK RESULTS FOR PLUMBING</b>			
BP 22.01 Plumbing	1.00 LS	932,990.00	932,990
<b>Total Minor Item Code 22010.000 COMMON WORK RESULTS FOR PLUMBING</b>			<b>\$932,990</b>
<b>Total Major Item Code 22000.000 PLUMBING WORK</b>			<b>\$932,990</b>
<b>Major Item Code 23000.000 HEATING, VENTILATION, &amp; AIR CONDITIONING</b>			
<b>Minor Item Code 23000.000 HVAC</b>			
BP 23.01 HVAC	1.00 LS	1,897,546.00	1,897,546
BP 23.01A Chillers & RTUs	1.00 LS	480,548.00	480,548
BP 23.02 HVAC T&B	1.00 INCL		
<b>Total Minor Item Code 23000.000 HVAC</b>			<b>\$2,378,094</b>
<b>Total Major Item Code 23000.000 HEATING, VENTILATION, &amp; AIR CONDITIONING</b>			<b>\$2,378,094</b>
<b>Major Item Code 26000.000 ELECTRICAL WORK</b>			
<b>Minor Item Code 26000.000 ELECTRICAL</b>			
BP 26.01 Electrical	1.00 LS	3,431,056.00	3,431,056
BP 26.01A Electrical Gear	1.00 LS	162,170.00	162,170



Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF

Secondary Project Qty: 0 FLRS

Estimate UM: Imperial

Report includes Taxes &amp; Insurance.

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			
BP 26.01B Generator	1.00 LS	140,311.00	140,311
Non-lit Focal Point Acoustical Baffle Allowance	1.00 ALLW	250,000.00	250,000
<b>Total Minor Item Code 26000.000</b>			<b>\$3,983,537</b>
<b>ELECTRICAL</b>			
<b>Total Major Item Code 26000.000</b>			<b>\$3,983,537</b>
<b>ELECTRICAL WORK</b>			
<b>Major Item Code 27000.000 COMMUNICATIONS SYSTEMS</b>			
<b>Minor Item Code 27000.000 COMMUNICATIONS SYSTEMS</b>			
BP 27.02 Audio / Video System	1.00 INCL		
<b>Total Minor Item Code 27000.000</b>			
<b>COMMUNICATIONS SYSTEMS</b>			
<b>Total Major Item Code 27000.000</b>			
<b>COMMUNICATIONS SYSTEMS</b>			
<b>Major Item Code 31000.000 SITEWORK</b>			
<b>Minor Item Code 31000.000 SITEWORK</b>			
BP 31.01 Sitework & Utilities	1.00 LS	1,370,356.00	1,370,356
Unsuitable Soil Relocation (Onsite / Building Pad)	1.00 ALLW	60,000.00	60,000
<b>Total Minor Item Code 31000.000</b>			<b>\$1,430,356</b>
<b>SITEWORK</b>			
<b>Total Major Item Code 31000.000 SITEWORK</b>			<b>\$1,430,356</b>
<b>Major Item Code 32000.000 SITE IMPROVEMENTS</b>			
<b>Minor Item Code 31650.000 SITE IMPROVEMENTS</b>			
BP 32.02 Unit Pavers	1.00 INCL		
<b>Total Minor Item Code 31650.000 SITE</b>			
<b>IMPROVEMENTS</b>			
<b>Minor Item Code 32900.000 LANDSCAPING</b>			
BP 32.03 Landscaping	1.00 LS	263,462.00	263,462
<b>Total Minor Item Code 32900.000</b>			<b>\$263,462</b>
<b>LANDSCAPING</b>			
<b>Total Major Item Code 32000.000 SITE</b>			<b>\$263,462</b>
<b>IMPROVEMENTS</b>			
<b>Major Item Code 35000.000 ALLOWANCES</b>			
<b>Minor Item Code 33900.000 ALLOWANCES</b>			
Addendum 2	1.00 ALLW	350,000.00	350,000
Building Permit Comments	1.00 ALLW	100,000.00	100,000
Owner Move Assist	1.00 ALLW	20,000.00	20,000
Temporary Protection Measures	1.00 ALLW	25,000.00	25,000
Public Art Related Construction Allowance	1.00 ALLW	40,000.00	40,000
<b>Total Minor Item Code 33900.000</b>			<b>\$535,000</b>
<b>ALLOWANCES</b>			
<b>Total Major Item Code 35000.000</b>			<b>\$535,000</b>
<b>ALLOWANCES</b>			
<b>Major Item Code 36000.000 BONDS &amp; INSURANCE</b>			
<b>Minor Item Code 36000.000 BONDS &amp; INSURANCE</b>			
Performance & Payment Bond	1.00 LS	216,038.00	216,038
General Liability	1.00 LS	310,740.00	310,740
Builder's Risk Insurance	1.00 NIC		
<b>Total Minor Item Code 36000.000 BONDS</b>			<b>\$526,778</b>
<b>&amp; INSURANCE</b>			

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF

Secondary Project Qty: 0 FLRS

Estimate UM: Imperial

Report includes Taxes &amp; Insurance.

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			
<b>Total Major Item Code 36000.000 BONDS &amp; INSURANCE</b>			<b>\$526,778</b>
<b>Major Item Code 37000.000 WARRANTIES</b>			
<b>Minor Item Code 37000.000 WARRANTY</b>			
Warranty Allocation	1.00 LS	11,838.00	11,838
<b>Total Minor Item Code 37000.000 WARRANTY</b>			<b>\$11,838</b>
<b>Total Major Item Code 37000.000 WARRANTIES</b>			<b>\$11,838</b>
<b>Major Item Code 50000.000 ESCALATION COSTS</b>			
<b>Minor Item Code 50000.000 ESCALATION COSTS</b>			
Pre-Purchase Refinement Allowance	1.00 ALLW	200,000.00	200,000
<b>Total Minor Item Code 50000.000 ESCALATION COSTS</b>			<b>\$200,000</b>
<b>Total Major Item Code 50000.000 ESCALATION COSTS</b>			<b>\$200,000</b>
<b>Major Item Code 80000.000 CONTINGENCY</b>			
<b>Minor Item Code 80000.000 CONTINGENCY</b>			
Contingency	1.00 LS	1,035,801.00	1,035,801
<b>Total Minor Item Code 80000.000 CONTINGENCY</b>			<b>\$1,035,801</b>
<b>Total Major Item Code 80000.000 CONTINGENCY</b>			<b>\$1,035,801</b>
<b>Major Item Code 95000.000 OVERHEAD &amp; FEES</b>			
<b>Minor Item Code 90000.000 OVERHEAD &amp; FEES</b>			
Contruction Managers Fee	1.00 LS	1,078,025.00	1,078,025
<b>Total Minor Item Code 90000.000 OVERHEAD &amp; FEES</b>			<b>\$1,078,025</b>
<b>Total Major Item Code 95000.000 OVERHEAD &amp; FEES</b>			<b>\$1,078,025</b>
<b>Total Sec BB BASE BID</b>			<b>\$29,605,458</b>

## ALLOWANCE SCHEDULE

The following allowances are included in the GMP Proposal where a clear scope has not been defined by the GMP Documents or where the items require further research. These allowances are for the cost of work only and do not include costs for insurance, bonds, contingency, fee, etc.

It is understood that the Construction Manager's Contract will require adjustments by change order (either additive or deductive) for reconciling the difference between each of the below listed allowances and the actual costs and/or savings realized for each allowance.

<u>Item No.</u>	<u>Description</u>	<u>Allowance Amount</u>
	<b>Division 06 – Wood, Plastics and Composites</b>	
06500.000 - 1	Ballistic Assembly @ Dais	\$50,000
	<b>Division 07 – Thermal and Moisture Protection</b>	
07410.000 - 1	Metal Panels Engineering & Coordination	\$125,000
	<b>Division 10 – Specialties</b>	
10000.000 - 1	Interior & Exterior Signage	\$57,896
	<b>Division 11 – Equipment</b>	
11000.000 - 1	Residential Appliance	\$30,000
	<b>Division 12 – Furnishings</b>	
12000.000 - 1	FF&E	\$750,000
	<b>Division 26 – Electrical</b>	
26000.000-1	Non-lit Focal Point Acoustical Baffles	\$250,000
	<b>Division 31 – Earthwork</b>	
31000.000-1	Unsuitable Soil Relocation (Onsite/Building Pad)	\$60,000
	<b>Division 35 - Allowances</b>	
35000.000-1	Addendum 2	\$350,000
35000.000-2	Building Permit Comment Modifications	\$100,000
35000.000-3	Owner Move Assistance	\$20,000
35000.000-4	Temporary Protective Measures	\$25,000
35000.000-4	Public Art Construction Related Work	\$40,000
	Pre-Purchase Refinement Allowance	\$200,000

**END OF ALLOWANCE SCHEDULE**

## **ALTERNATES NARRATIVE**

Within this section we have included pricing for various Alternates for consideration by City of Clearwater. At this time, none of these Alternates are included within the Base Bid GMP Proposal. The pricing for each alternate represents the adjustment required to the Base Bid GMP Proposal to incorporate the proposed change in scope. A summary listing of the proposed alternates is listed below. A more detailed description and a detailed cost report for each alternate have been provided immediately following this narrative. The pricing provided includes all applicable mark-ups for bonds, insurance, etc.

- |   |     |                  |
|---|-----|------------------|
| ▪ Alternate No. 1 – PV Panels & Sacrificial Roof at Solar Array | Add | <b>\$333,056</b> |
|---|-----|------------------|

The Alternate Pricing provided is guaranteed through December 19, 2024, or as indicated otherwise in this proposal, at which time the pricing and feasibility for the proposed change in scope would require an updated evaluation.

Note: The proposed change in scope and related pricing for various Alternates may be overlapping in nature and may require revisions based on the combination of Alternates accepted.

**ALTERNATE NO. 1**

**Alternate Narrative: Alternate No. 1 – PV Panels & Sacrificial Roof at Solar Array**

Provide complete Solar Stack PV system and sacrificial roof membrane to allow for installation of pedestals for roof solar array installation.

**Adjustment to the Base Bid GMP:**                      **Add**                                      **\$333,056**

Note: A copy of the CM Detail Cost Report related to this alternate is attached and immediately follows this narrative.

**Adjustment to the Contract Time:**                      **Add/Deduct**                                      **0 Calendar Days**

Sort Sequences:

1. Sec
2. Major Item Code
3. Not Used
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.es

Estimator:

Primary Project Qty:0

Secondary Project Qty: 0 FLF

Estimate UM: Imperi

**Report includes Taxes & Insurance.**

2:59:21PM

9/24/2024

Description	Unit\$	Total \$
-------------	--------	----------

**NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!**

<b>Total Major Item Code 03600.000 GROUT</b>		<b>\$60,000</b>
<b>Total Major Item Code 26000.000 ELECTRICAL WORK</b>		<b>\$240,000</b>
<b>Total Major Item Code 36000.000 BONDS &amp; INSURANCE</b>		<b>\$5,928</b>
<b>Total Major Item Code 37000.000 WARRANTIES</b>		<b>\$133</b>
<b>Total Major Item Code 50000.000 ESCALATION COSTS</b>		<b>\$3,331</b>
<b>Total Major Item Code 80000.000 CONTINGENCY</b>		<b>\$11,657</b>
<b>Total Major Item Code 95000.000 OVERHEAD &amp; FEES</b>		<b>\$12,007</b>
<b>Total Sec Z01 ALTERNATE 1</b>		<b>\$333,056</b>

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF

Secondary Project Qty: 0 FLRS

Estimate UM: Imperial

Report includes Taxes &amp; Insurance.

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
-------------	----------	---------	----------

**NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!**

**Sec Z01 ALTERNATE 1****Major Item Code 03600.000 GROUT****Minor Item Code 03600.000 GROUT**

Sacrificial Roof at Solar Array 1.00 LS 60,000.00 60,000

**Total Minor Item Code 03600.000 GROUT****\$60,000****Total Major Item Code 03600.000 GROUT****\$60,000****Major Item Code 26000.000 ELECTRICAL WORK****Minor Item Code 26000.000 ELECTRICAL**

Solar Panel System - 120kW 1.00 LS 240,000.00 240,000

**Total Minor Item Code 26000.000****\$240,000****ELECTRICAL****Total Major Item Code 26000.000****\$240,000****ELECTRICAL WORK****Major Item Code 36000.000 BONDS & INSURANCE****Minor Item Code 36000.000 BONDS & INSURANCE**

Performance & Payment Bond 1.00 LS 2,431.00 2,431

General Liability 1.00 LS 3,497.00 3,497

Builder's Risk Insurance 1.00 NIC

**Total Minor Item Code 36000.000 BONDS****\$5,928****& INSURANCE****Total Major Item Code 36000.000 BONDS &****\$5,928****INSURANCE****Major Item Code 37000.000 WARRANTIES****Minor Item Code 37000.000 WARRANTY**

Warranty Allocation 1.00 LS 133.00 133

**Total Minor Item Code 37000.000****\$133****WARRANTY****Total Major Item Code 37000.000****\$133****WARRANTIES****Major Item Code 50000.000 ESCALATION COSTS****Minor Item Code 50000.000 ESCALATION COSTS**

Escalation Costs 1.00 LS 3,331.00 3,331

**Total Minor Item Code 50000.000****\$3,331****ESCALATION COSTS****Total Major Item Code 50000.000****\$3,331****ESCALATION COSTS****Major Item Code 80000.000 CONTINGENCY****Minor Item Code 80000.000 CONTINGENCY**

Contingency 1.00 LS 11,657.00 11,657

**Total Minor Item Code 80000.000****\$11,657****CONTINGENCY****Total Major Item Code 80000.000****\$11,657****CONTINGENCY****Major Item Code 95000.000 OVERHEAD & FEES****Minor Item Code 90000.000 OVERHEAD & FEES**

Overhead & Fee 1.00 LS 12,007.00 12,007

**Total Minor Item Code 90000.000****\$12,007****OVERHEAD & FEES**

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :24.079\_CLEARWATER CITY HALL \_GMP\_03.est - ,

Estimator:

Primary Project Qty:0 SF

Secondary Project Qty: 0 FLRS

Estimate UM: Imperial

**Report includes Taxes & Insurance.**

3:01:09PM

9/24/2024

Description	Quantity	Unit \$	Total \$
-------------	----------	---------	----------

**NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!**

**Total Major Item Code 95000.000 OVERHEAD  
& FEES**

**\$12,007**

**Total Sec Z01 ALTERNATE 1**

**\$333,056**





## **GMP GENERAL CONDITIONS / GENERAL REQUIREMENTS SUMMARY**

## Cost Management Recap



Sort Sequences:

1. Sec
2. Major Item Code
3. Not Used
4. Not Used

Estimate File: :CLEARWATER CITY HALL GMP 03\_00.est - CIT'  
CLEARWATER CITY HALL ERP 1, 761 PIERCE STREET, CLEARWATE

Estimator: WES STEVEN

Primary Project Qty:0 \$

Secondary Project Qty: 0 FLF

Estimate UM: Imperi:

**Report includes Taxes & Insurance.**

12:13:27PM

9/24/2024

Description	Unit\$	Total \$
<b><u>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!</u></b>		
<b>Total Major Item Code 01300.000</b>		<b>\$1,898,167</b>
<b>GENERAL CONDITIONS</b>		
<b>Total Major Item Code 01300.300</b>		<b>\$589,566</b>
<b>GENERAL REQUIREMENTS</b>		
<b>Total Sec BB BASE BID</b>		<b>\$2,487,733</b>

# Cost Management Detail



Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :CLEARWATER CITY HALL GMP 03\_00.est - CITY OF CLEARWATER CITY HALL  
761 PIERCE STREET, CLEARWATER, FL

Estimator: WES STEVENS

Primary Project Qty: 0 SF

Secondary Project Qty: 0 FLRS

Estimate UM: Imperial

**Report includes Taxes & Insurance.**

12:15:05PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			

## Sec BB BASE BID

### Major Item Code 01300.000 GENERAL CONDITIONS

#### Minor Item Code 01300.000 ADMINISTRATIVE REQUIREMENTS

Project Executive (Part Time)	83.00 WEEK	260.00	21,580
Project Executive Vehicle Allowance	19.00 MO	64.80	1,231
Operations Manager (Part Time)	83.00 WEEK	876.00	72,708
Operations Manager Vehicle Allowance	19.00 MO	162.40	3,086
Senior Project Manager	96.00 WEEK	3,611.92	346,745
Senior Project Manager Vehicle Allowance	22.00 MO	640.00	14,080
Asst. Project Manager	96.00 WEEK	3,228.85	309,969
Asst. Project Manager Vehicle Allowance	22.00 MO	650.00	14,300
General Superintendent (Part Time)	83.00 WEEK	1,059.33	87,924
General Superintendent Vehicle Allowance	19.00 MO	117.60	2,234
Full Time Project Superintendent	96.00 WEEK	4,315.15	414,254
Asst. Superintendent #1	83.00 WEEK	2,754.35	228,611
MEP Superintendent	48.00 WEEK	2,387.10	114,581
Full Time Project Engineer #1	52.00 WEEK	1,836.24	95,484
Project Accountant	96.00 WEEK	175.20	16,819
Jobsite Secretary	96.00 WEEK	1,460.00	140,160
Home Office Secretary	96.00 WEEK	150.00	14,400
Watchmen	1.00 NIC		

**Total Minor Item Code 01300.000**

**\$1,898,167**

#### ADMINISTRATIVE REQUIREMENTS

**Total Major Item Code 01300.000 GENERAL CONDITIONS**

**\$1,898,167**

### Major Item Code 01300.300 GENERAL REQUIREMENTS

#### Minor Item Code 01310.000 TRAVEL, PER DIEM, & RELOCATION

Travel Expenses	22.00 MO	160.50	3,531
-----------------	----------	--------	-------

**Total Minor Item Code 01310.000**

**\$3,531**

#### TRAVEL, PER DIEM, & RELOCATION

#### Minor Item Code 01320.000 CONSTRUCTION PROGRESS DOCUMENTATION

Open Space/Cubix Application	1.00 LS	15,000.00	15,000
Aerial Photographs	19.00 MO	125.00	2,375
Construction Schedule	19.00 MO	75.00	1,425

**Total Minor Item Code 01320.000**

**\$18,800**

#### CONSTRUCTION PROGRESS DOCUMENTATION

#### Minor Item Code 01350.000 SPECIAL PROCEDURES

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :CLEARWATER CITY HALL GMP 03\_00.est - CITY OF CLEARWATER CITY HALL  
 761 PIERCE STREET, CLEARWATER, FL  
 Estimator: WES STEVENS  
 Primary Project Qty: 0 SF  
 Secondary Project Qty: 0 FLRS  
 Estimate UM: Imperial

**Report includes Taxes & Insurance.**

12:15:05PM

9/24/2024

Description	Quantity	Unit \$	Total \$
<b>NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!</b>			
Project Document Management Software	1.00 LS	27,000.00	27,000
Virtual/ShareFile	19.00 MO	188.50	3,582
Data Processing	22.00 MO	250.00	5,500
<b>Total Minor Item Code 01350.000</b>			<b>\$36,082</b>
<b>SPECIAL PROCEDURES</b>			
<b>Minor Item Code 01410.000 REGULATORY REQUIREMENTS</b>			
Transportation Impact Fees	1.00 NIC		
Impact/Connection Fees	1.00 NIC		
<b>Total Minor Item Code 01410.000</b>			
<b>REGULATORY REQUIREMENTS</b>			
<b>Minor Item Code 01420.000 SAFETY</b>			
First Aid Supplies	1.00 LS	428.00	428
Safety Supplies	19.00 MO	123.05	2,338
Safety Jobsite Signs	20.00 EACH	68.10	1,362
Safety Incentives	19.00 MO	100.00	1,900
Safety Director / Inspector	83.00 WEEK	224.62	18,644
Temporary Fire Protection (1 ea / 6,000 Sf)	8.00 EA	96.04	768
Water, Ice, & Cups	22.00 MO	37.45	824
<b>Total Minor Item Code 01420.000 SAFETY</b>			<b>\$26,264</b>
<b>Minor Item Code 01430.000 QUALITY ASSURANCE</b>			
Threshold Inspector	1.00 NIC		
Punch List (Misc. Materials)	1.00 LS	7,500.00	7,500
<b>Total Minor Item Code 01430.000</b>			<b>\$7,500</b>
<b>QUALITY ASSURANCE</b>			
<b>Minor Item Code 01500.000 TEMPORARY FACILITIES</b>			
Project Office Trailer	20.00 MO	2,675.00	53,500
Office Trailer Set-up	2.00 EACH	3,680.00	7,360
Office Trailer Removal	2.00 EACH	3,023.00	6,046
Project Tool House	19.00 MO	240.75	4,574
Tool House Set-up & Removal	1.00 EACH	386.25	386
General Purpose Laborer	83.00 WEEK	800.00	66,400
General Purpose Carpenter	30.00 WEEK	1,335.90	40,077
A/E Trailer & Equipment	1.00 NIC		
Project Office Supplies	22.00 MO	267.50	5,885
Jobsite Office Supply Set-up	1.00 LS	800.00	800
Jobsite Postage	22.00 MO	160.50	3,531
Jobsite Office Equipment	22.00 MO	1,250.00	27,500
Jobsite Office Furniture	22.00 MO	400.00	8,800
Jobsite Water Cooler	22.00 MO	80.25	1,766
<b>Total Minor Item Code 01500.000</b>			<b>\$226,625</b>
<b>TEMPORARY FACILITIES</b>			
<b>Minor Item Code 01510.000 TEMPORARY UTILITIES</b>			
Temporary Wiring	1.00 LS	1,500.00	1,500
Chemical Toilets	19.00 MO	930.90	17,687
Electric Usage Charge	19.00 MO	535.00	10,165
Temporary Electric Connection	1.00 LS	3,000.00	3,000
Water Usage Charge	19.00 MO	235.40	4,473
Early Cut-On Permanent Power	1.00 NIC		
<b>Total Minor Item Code 01510.000</b>			<b>\$36,825</b>
<b>TEMPORARY UTILITIES</b>			

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :CLEARWATER CITY HALL GMP 03\_00.est - CITY OF CLEARWATER CITY HALL  
 761 PIERCE STREET, CLEARWATER, FL  
 Estimator: WES STEVENS  
 Primary Project Qty: 0 SF  
 Secondary Project Qty: 0 FLRS  
 Estimate UM: Imperial

**Report includes Taxes & Insurance.**

12:15:05PM

9/24/2024

Description	Quantity	Unit \$	Total \$
-------------	----------	---------	----------

**NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!**

**Minor Item Code 01530.000 PROJECT COMMUNICATIONS**

Internet Service Charges	22.00 MO	325.00	7,150
Jobsite Communications	22.00 MO	856.00	18,832

**Total Minor Item Code 01530.000**

**\$25,982**

**PROJECT COMMUNICATIONS**

**Minor Item Code 01540.000 CONSTRUCTION TOOLS & EQUIPMENT**

Small Tools & Equipment	22.00 MO	250.00	5,500
Superintendent Pick-up Truck	22.00 MO	749.00	16,478
Fuel for Superintendent Pick-up Truck	22.00 MO	300.00	6,600
MEP Superintendent Pick-up Truck	11.00 MO	561.75	6,179
Fuel for MEP Superintendent Pick-up Truck	11.00 MO	280.87	3,090
Fork Lift - 2.5 Ton, 4 WD	8.00 MO	2,050.00	16,400
Fork Lift Operator	35.00 WEEK	292.00	10,220
Fuel, Oil, & Lube for Forklift	8.00 MO	374.50	2,996
Temporary Stairs	3.00 FLRS	2,500.00	7,500

**Total Minor Item Code 01540.000**

**\$74,963**

**CONSTRUCTION TOOLS & EQUIPMENT**

**Minor Item Code 01560.000 TEMPORARY BARRIERS & ENCLOSURES**

Temporary Protection	1.00 LS	5,940.00	5,940
Safety Rails Maintenance	1.00 LS	7,921.00	7,921

**Total Minor Item Code 01560.000**

**\$13,861**

**TEMPORARY BARRIERS & ENCLOSURES**

**Minor Item Code 01570.000 TEMPORARY CONTROLS**

Security Badging Requirements	1.00 NIC		
Trailer Security System	19.00 MO	150.00	2,850

**Total Minor Item Code 01570.000**

**\$2,850**

**TEMPORARY CONTROLS**

**Minor Item Code 01580.000 PROJECT IDENTIFICATION**

Project Sign	1.00 EACH	1,080.50	1,081
Jobsite Signage	1.00 LS	613.00	613

**Total Minor Item Code 01580.000**

**\$1,694**

**PROJECT IDENTIFICATION**

**Minor Item Code 01590.000 I.C.R.A. REQUIREMENTS**

Trash Cart W/Lid	16.00 MO	60.00	960
------------------	----------	-------	-----

**Total Minor Item Code 01590.000 I.C.R.A.**

**\$960**

**REQUIREMENTS**

**Minor Item Code 01720.000 CONSTRUCTION PREPARATION**

Purchase Drawings/Reproduction Cost	1.00 LS	5,350.00	5,350
Layout Supplies	8.00 WEEK	267.50	2,140
Layout Labor	8.00 WEEK	667.00	5,336

**Total Minor Item Code 01720.000**

**\$12,826**

**CONSTRUCTION PREPARATION**

**Minor Item Code 01740.000 PROJECT CLEANING**

Construction Clean-up	2,080.00 MNHR	24.90	51,792
Rubbish Removal	19.00 MO	64.20	1,220
Dump Charges	2,025.00 CUYD	19.53	39,543

**Total Minor Item Code 01740.000**

**\$92,555**

**PROJECT CLEANING**

Sort Sequences:

1. Sec
2. Major Item Code
3. Minor Item Code
4. Not Used

Estimate File: :CLEARWATER CITY HALL GMP 03\_00.est - CITY OF CLEARWATER CITY HALL  
761 PIERCE STREET, CLEARWATER, FL  
Estimator: WES STEVENS  
Primary Project Qty:0 SF  
Secondary Project Qty: 0 FLRS  
Estimate UM: Imperial

**Report includes Taxes & Insurance.**

12:15:05PM

9/24/2024

Description	Quantity	Unit \$	Total \$
-------------	----------	---------	----------

**NOTICE : This Document is considered proprietary information and shall not be distributed beyond the intended recipient without the express written consent of Ajax Building Company, LLC !!!**

**Minor Item Code 01770.000 CLOSEOUT PROCEDURES**

As-Built Drawings - Red Line Copies	1.00 LS	750.00	750
<b>Total Minor Item Code 01770.000</b>			<b>\$750</b>

**CLOSEOUT PROCEDURES**

**Minor Item Code 01820.000 DEMONSTRATION & TRAINING**

Video Tape Training	1.00 LS	7,500.00	7,500
<b>Total Minor Item Code 01820.000</b>			<b>\$7,500</b>

**DEMONSTRATION & TRAINING**

<b>Total Major Item Code 01300.300 GENERAL</b>			<b>\$589,566</b>
--	--	--	------------------

**REQUIREMENTS**

<b>Total Sec BB BASE BID</b>			<b>\$2,487,733</b>
------------------------------	--	--	--------------------

**CM FEE CALCULATION CHECK SHEET**

City of Clearwater New City Hall					
GMP 2 - Final					
Fee Check Sheet					
		<b>FEE CHECK</b>			
<b>GMP AMOUNT</b>	<b>\$29,605,458</b>				
<b>LESS FOLLOWING ELEMENTS:</b>					
<b>PRECON FEE</b>	Not Included				
<b>BONDS</b>	-\$216,038		0.73%	Of GMP Total	
<b>GL INSURANCE</b>	-\$310,740		1.05%	Of GMP Total	
<b>FEE</b>	-\$1,078,025				
<b>Subtotal</b>	<b>\$28,000,655</b>				
<b>FEE at 3.8%</b>	<b>\$1,078,025</b>	<b>\$1,078,025</b>			

## **LOGISTICS PLAN NARRATIVE**

Refer to the attached Site Utilization Plan dated January 30, 2024 as prepared by Ajax Building Company, LLC and included in Section V-B of this proposal for the illustration of the below listed items.

### Temporary Fencing

- Material: Six foot (6') high galvanized chain link fencing will be utilized for the temporary construction fencing.
- Locations: Temporary fencing will be installed at the locations indicated on the Site Utilization Plan.
- Visual Barriers: Full-height windscreening will be installed as a visual barrier on all chain link fencing and gates. This visual barrier will be maintained for the duration of the project.

### Construction Entrances and Temporary Gates

- Primary Construction Entrance: The primary construction entrance is located at Pierce Street. A 24' wide vehicle gate will be located at this entrance.
- Secondary Construction Entrances: Secondary entrances to the project site will be located Franklin Street. A 24' wide vehicle gates will be located at these entrances. These entrances will serve as secondary and emergency access to the project site.
- All construction entrances intended for vehicular traffic will be stabilized with gravel, limerock, crushed concrete, asphalt millings, or other stabilization materials as determined appropriate by Ajax Building Company, LLC. Although it is anticipated that a large portion of the stabilization materials will be inherently absorbed by the project site, Ajax Building Company, LLC will endeavor to remove and dispose of these stabilization materials to a practical limit prior to the installation of site finishes.
- Note: The locations for all gates are indicated on the Site Utilization Plan.

### Site Security

- Gate Security: All temporary gates, vehicle and pedestrian, will be chained and locked during non-work hours throughout the duration of the project.
- Considerations for a night watchman are not included.

### Debris Removal

- Roll-off containers will be supplied and maintained by Ajax Building Company, LLC for removing construction debris from the project site.
- All roll-off container pulls will be scheduled by Ajax Building Company, LLC's Project Superintendent.
- Unless otherwise dictated by the progress/requirements of the project, Ajax Building Company, LLC will endeavor to perform all roll-off container pulls during business hours.

### Tree Protection / Erosion Control / Barricades

- Tree protection: All tree protection required by the Contract Documents will be installed prior to the commencement of site work.
- Erosion Control: All silt fencing, hay bales and other erosion control measures required by the Contract Documents will be installed prior to the commencement of site work.
- Tree and Root Pruning: All tree and root pruning required will be performed in accordance with the Contract Documents.



Crane, Vehicle and Equipment Paths

- Crane, vehicle and equipment paths required for equipment and/or vehicle travel, bearing, access, etc. within the project site will be stabilized with gravel, limerock, crushed concrete, asphalt millings, or other stabilization materials as determined appropriate by Ajax Building Company, LLC.
- Although it is anticipated that a large portion of the stabilization materials will be inherently absorbed by the project site, Ajax Building Company, LLC will endeavor to remove and dispose of these stabilization materials to a practical limit prior to the installation of site finishes.

On-Site Material Storage

- Storage Containers: Various materials, equipment and fabricated items will be stored in Connex-type trailers, tractor trailers and storage boxes within the fenced area of the project site. All storage containers will be locked during non-work hours.
- Open Material Storage: Various materials, equipment and fabricated items that do not lend themselves to be stored in containers will be stored and/or staged on the project site. Such items will be stored on dunnage and protected from the elements as necessary to ensure that the quality and condition of the items is not jeopardized.

Temporary Facilities

- Jobsite Office Trailers: The locations for jobsite office trailers are indicated on the Site Utilization Plan. The locations indicated have been proposed in an effort to minimize interference with construction activities and to allow for minimal disturbance of the completed construction when the office trailers are removed at the completion of the project. All jobsite office trailers will be well-maintained units.
- Schedule: The project schedule indicates that the mobilization of jobsite office trailers will commence in September 2024 with the start of mobilization activities.
- Temporary Power:
  - Temporary electrical service for the jobsite office trailers will be obtained from Duke Energy. The temporary electrical service is being provided by Duke Energy and will be installed by the Electrical Subcontractor
  - Temporary electrical service for the construction site will be obtained from Duke Energy. The temporary electrical service is being provided by Duke Energy and will be installed by the Electrical Subcontractor.
- Temporary Water:
  - Temporary water service for the jobsite office trailers will be obtained from the City of Clearwater. The temporary water service is being provided by the City of Clearwater and will be installed by the Plumbing Subcontractor.
  - Temporary water service for the construction site will be obtained from the City of Clearwater. The temporary water service is being provided by the City of Clearwater and will be installed by the Plumbing Subcontractor.
- Temporary Sanitary Sewer:
  - The temporary sanitary sewer service for the jobsite office trailers will be obtained by supplying a sanitary holding tank.
  - The temporary sanitary sewer service for the construction site will be obtained by 2) supplying portable toilet facilities (port-o-lets).

- In such cases that a holding tank or portable toilet facilities (port-o-lets) are required, those facilities will be serviced two (2) times per week or as otherwise necessary when they are in use.
- Temporary Telephone and Internet Services:
  - Temporary telephone service for the jobsite office trailers will be obtained from TBD. The temporary telephone service is being provided by TBD and will be installed by the Electrical Subcontractor
  - Temporary internet service for the jobsite office trailers will be obtained from TBD. The temporary internet service is being provided by TBD and will be installed by the Electrical Subcontractor.

Construction Traffic, Parking and Deliveries

- Ajax Building Company, LLC Office Staff: Ajax office staff will utilize the Pierce Street entrance gate and drive for access, parking and project management activities. Parking for Ajax office staff will be in the location(s) indicated on the Site Utilization Plan.
- Construction Employees and Personnel: Construction employees and personnel will utilize the Pierce Street entrance gate and drive for access and parking. Parking for construction employees and personnel will be in the location(s) indicated on the Site Utilization Plan.
- Construction Deliveries: General construction related deliveries will utilize the Pierce Street Entrance gate and drive for access to the project site.
- Considerations for offsite parking are not included in the ERP GMP Proposal.

Maintenance of Site

- Ajax Building Company, LLC will maintain all temporary fencing, visual windscreen barriers, tree protection, erosion control measures, construction storage areas, and construction parking areas to ensure safety and an acceptable appearance. It is assumed that the Owner will continue to maintain all other areas outside the construction site or not occupied by Ajax Building Company, LLC.
- Street sweeping will be performed as necessary.
- The site will be monitored for trash, debris, and general housekeeping. Cleanup and housekeeping will be performed on a regular basis as necessary to ensure safety and an acceptable appearance.

Emergency Contact Information

- Emergency Contacts: The following is a list of emergency contact numbers for Ajax Building Company, LLC personnel assigned to the project.

<u>Contact Person</u>	<u>Job Title</u>	<u>Contact Number</u>
Tim Sewell	Regional Director	813-539-0551
Chris Brown	Senior Project Manager	813-539-2771
Allison Feldsott	Project Manager	813-285-3077





January 30, 2024

Logistics Plan  
Clearwater City Hall

**Ajax**



## **SCHEDULE NARRATIVE**

Refer to the attached Master Project Schedule dated September 16, 2024 as prepared by Ajax Building Company, LLC and included in Section VI-B of this proposal for the illustration of the below listed items. The project schedule has been updated to include progress achieved through September 16, 2024.

The project schedule included within this proposal is based on the information represented in the GMP Documents. The project schedule reflects an overall duration of twenty-two (22) months for the construction phase of the project.

The following contractual dates are incorporated into the CM Contract via this GMP Proposal.

- |                          |                   |
|--------------------------|-------------------|
| ▪ Substantial Completion | June 8, 2026      |
| ▪ Final Completion       | September 1, 2026 |

The following additional Milestone Dates are anticipated within the project schedule in order to achieve the contractual dates listed above.

- |  |                    |
|--|--------------------|
| ▪ Mobilization / Start of Construction | September 30, 2024 |
| ▪ Top-Out of Building Structure        | June 12, 2025      |
| ▪ Building Dry-In                      | November 10, 2025  |
| ▪ Permanent Power                      | November 19, 2025  |
| ▪ Owner Occupancy                      | August 24, 2026    |

In order for Mobilization activities to commence on September 30, 2024 as scheduled, the following contractual activities will need to be completed as indicated.




- |                                  |                    |
|----------------------------------|--------------------|
| ▪ GMP Negotiations Complete      | September 23, 2024 |
| ▪ CM Contract Amendment Executed | October 3, 2024    |
| ▪ Notice to Proceed Issued       | October 4, 2024    |
| ▪ All Required Permits Issued    | October 11, 2024   |

In order to expedite the project start-up activities, the Design Team, the Construction Manager and the Owner will be required to closely coordinate and expedite submittal review/approval, respond to information requests, respond to conflicts/unforeseen conditions, etc.

The schedule is based upon the assumption that any design revisions required to address future design review comments and/or permitting review comments will be issued to the Construction Manager within one (1) week of receipt of such comments with a directive to proceed. It is further assumed that such revisions (if any) will be minor in nature and will not result in a material change in the overall scope and/or direction of the project.

Ajax Building Company, LLC will continue to work closely with the Project Team throughout the Preconstruction and Construction Phases of the project to ensure that all critical dates are maintained.

Activity ID	Activity Name	Original Start	Finish
<b>City of Clearwater City Hall - 9/16/2024</b>		1041	01-Sep-23
		01-Sep-26	
<b>CM Contract Activities</b>		5	03-Nov-23
CM-1000	CM Selection by City	0	03-Nov-23
CM-1010	Project Kickoff Meeting	0	21-Nov-23
CM-1020	CM Contract Negotiations	5	21-Nov-23
CM-1030	Prepare Final Contract Documents for Council	5	08-Dec-23
CM-1040	Council Approval of CM Contract	0	19-Dec-23 A
<b>City Hall Preconstruction Services</b>		583	01-Sep-23
		11-Oct-24	
<b>30% Schematic Design</b>		425	01-Sep-23
		02-Feb-24 A	
PRE-1000	Prepare 30% Schematic Design Documents	60	01-Sep-23
PRE-1010	Owner Review 30% Schematic Design Docur	10	01-Nov-23
PRE-1030	Owner Page Turn 30% Documents	0	14-Nov-23 A
PRE-1070	CM 30% Schematic Estimate	15	05-Jan-24 A
<b>60% Design Development</b>		94	15-Nov-23
		08-Apr-24 A	
PRE-1040	Prepare 60% Design Development Documents	60	15-Nov-23
PRE-1110	Owner Review 60% Design Development Docu	10	01-Mar-24 A
PRE-1120	CM 60% Design Development Estimate	5	01-Mar-24 A
PRE-1140	Owner Page Turn 60% Design Development D	0	15-Mar-24 A
<b>90% Construction Documents</b>		82	15-Mar-24 A
		24-Jul-24 A	
PRE-1150	Prepare 90% Construction Documents	60	15-Mar-24 A
PRE-1160	Owner Review 90% Documents (Permit / Bid I	15	05-Jul-24 A
<b>100% Construction Documents</b>		22	24-Jul-24 A
		23-Aug-24 A	
PRE-1170	Prepare 100% Construction Documents (Adde	22	24-Jul-24 A
<b>Permitting</b>		95	03-Jun-24 A
		11-Oct-24	
<b>ERP Building Permit</b>		20	08-Jul-24 A
		20-Sep-24	
PMT-1030	CM Submit Building Permit Application	0	08-Jul-24 A
PMT-1070	City Review and Comments	20	08-Jul-24 A
PMT-1080	Design Team Response to City Comments	10	26-Aug-24
PMT-1090	Final City Review and Approval	20	05-Sep-24
<b>Civil Permitting</b>		95	03-Jun-24 A
		11-Oct-24	
<b>SWFWMD Permit</b>		74	03-Jun-24 A
		11-Oct-24	
PMT-1000	Submit SWFWMD ERP Modification Application	0	03-Jun-24 A
PMT-1060	SWFWMD Review and Comment	65	03-Jun-24 A
PMT-1100	Additional Testing / EOR Response to SWFWI	29	08-Jul-24 A
PMT-1110	SWFWMD Review / Permit Issuance	25	15-Aug-24
<b>FDEP Permit</b>		45	03-Jul-24 A
		27-Sep-24	
PMT-1010	Submit Permit Application	0	03-Jul-24 A
PMT-1020	FDEP Sanitary & Water Review & Approval	45	05-Jul-24 A
<b>FDOT ROW Use Permit</b>		45	05-Jul-24 A
		27-Sep-24	
PMT-1050	FDOT Permit Review	45	05-Jul-24 A
PMT-1040	Submit FDOT Permit	0	16-Sep-24
<b>GMP Phase</b>		25	05-Jul-24 A
		04-Oct-24	
<b>GMP - 90% Documents</b>		25	05-Jul-24 A
		04-Oct-24	
GMP-1000	Prepare GMP Bid Packages	10	05-Jul-24 A
GMP-1020	GMP Bid Phase	25	18-Jul-24 A
GMP-1010	Pre Bid Conferences	2	01-Aug-24
GMP-1030	City Review & Comment - 100% CDs	5	26-Aug-24
GMP-1040	CM Review & RFIs - 100% CDs	5	26-Aug-24
GMP-1060	GMP CM Scope Review	5	28-Aug-24
GMP-1070	Prepare Final GMP	7	03-Sep-24
GMP-1050	Submit / Review Draft GMP	5	16-Sep-24
GMP-1080	Submit GMP	0	23-Sep-24
GMP-1090	GMP City Review / Council Board Prep	5	24-Sep-24
GMP-1100	GMP Staff Approval & Board Packet Preparati	4	30-Sep-24
GMP-1110	GMP City Council Approval	0	03-Oct-24
GMP-1120	GMP Notice to Proceed	0	04-Oct-24
<b>Early Release GMP Documents</b>		494	01-Nov-23
		26-Jul-24 A	
PRE-1020	Prepare ERP Documents	45	01-Nov-23
PRE-1050	Owner Review ERP Documents	10	15-Dec-23
PRE-1060	ERP Bidding Period	0	29-Dec-23

 Actual Work  
 Remaining Work  
 Critical Remaini...

Page 69




City of Clearwater City Hall - 9/16/2024

Start Date: 01-Sep-23  
Finish Date: 01-Sep-26

Page 1 of 13



Activity ID	Activity Name	Original Start	Finish
PRE-1080	CM Prepare ERP GMP	5/22-Jan-24 A	26-Jan-24 A
PRE-1090	Owner Review ERP GMP	5/29-Jan-24 A	02-Feb-24 A
PRE-1100	ERP GMP Packet to City for Council Agenda	8/06-Feb-24 A	15-Feb-24 A
PRE-1130	City Coucil Approval of ERP GMP	0	15-Feb-24 A
PRE-2000	ERP 1 Drawings Revisions - Addendum 1	35/29-Feb-24 A	05-Apr-24 A
PRE-2010	Update ERP 1 Pricing - Addendum 1	10/05-Apr-24 A	19-Apr-24 A
PRE-2020	ERP 1 Drawings Revisions - Addendum 2	35/17-Apr-24 A	08-May-24 A
PRE-2030	Update ERP 1 Pricing - Addendum 2	10/09-May-24	03-Jul-24 A
PRE-2040	Additional ERP Pricing - Owner Comments	15/05-Jul-24 A	26-Jul-24 A
Subcontracts and Procurement		358/25-Jun-24 A	09-Feb-26
<b>ERP GMP - Subcontract Award</b>		10/25-Jun-24 A	11-Sep-24 A
AWD-1030	Award / Issue Electrical Gear Direct Purchase	10/25-Jun-24 A	06-Aug-24 A
AWD-1050	Award / Issue Generator Direct Purchase Purc	10/25-Jun-24 A	11-Sep-24 A
AWD-1040	Award / Issue HVAC Equipment Direct Purcha	10/05-Jul-24 A	02-Aug-24 A
AWD-1020	Award / Issue Elevator Subcontract	10/29-Jul-24 A	30-Aug-24 A
AWD-1010	Award / Issue Sitework Subcontract	10/05-Aug-24	30-Aug-24 A
<b>ERP GMP - Submittals &amp; Procurement</b>		232/02-Aug-24	05-Aug-25
<b>Elevator Submittals</b>		232/30-Aug-24	05-Aug-25
SUB-1010	Prepare & Submit Elevators	40/30-Aug-24	25-Oct-24
SUB-1130	CM Review & Approve Elevators	10/28-Oct-24	08-Nov-24
SUB-1140	Arch/Eng Review & Approve Elevators	12/11-Nov-24	26-Nov-24
SUB-1150	Fab & Deliver Elevators	180/27-Nov-24	05-Aug-25
<b>HVAC Submittals</b>		198/02-Aug-24	18-Jun-25
SUB-4000	Prepare & Submit HVAC Equipment	8/02-Aug-24	09-Sep-24 A
SUB-4010	CM Review & Approve HVAC Equipment	7/09-Sep-24	18-Sep-24
SUB-4020	ARCH/ENG Review & Approve HVAC Equipm	15/19-Sep-24	09-Oct-24
SUB-4030	Fab & Deliver HVAC Chillers	180/10-Oct-24	18-Jun-25
SUB-4040	Fab & Deliver AHUs	150/10-Oct-24	07-May-25
<b>Electrical Gear Submittals</b>		174/07-Aug-24	15-May-25
SUB-1020	Prepare & Submit Electrical Gear	15/07-Aug-24	20-Sep-24
SUB-1050	CM Review & Approve Eletrical Gear	7/23-Sep-24	01-Oct-24
SUB-1080	Arch/Eng Review & Approve Electrical Gear	12/02-Oct-24	17-Oct-24
SUB-1110	Fab & Deliver Electrical Gear	150/18-Oct-24	15-May-25
<b>Generator Submittals</b>		192/12-Sep-24	10-Jun-25
SUB-1030	Prepare & Submit Generator	15/12-Sep-24	02-Oct-24
SUB-1060	CM Review & Approve Generator	7/03-Oct-24	11-Oct-24
SUB-1090	Arch/Eng Review & Approve Generator	12/14-Oct-24	29-Oct-24
SUB-1120	Fab & Deliver Generator	160/30-Oct-24	10-Jun-25
<b>Sitework &amp; Utilities Submittals</b>		57/30-Aug-24	03-Dec-24
SUB-1000	Prepare & Submit Utilities & Structures	15/30-Aug-24	27-Sep-24
SUB-1040	CM Review & Approve Utilities & Structures	5/30-Sep-24	04-Oct-24
SUB-1070	Arch/Eng Review & Approve Utilities & Structu	12/07-Oct-24	22-Oct-24
SUB-1100	Fab & Deliver Utilities & Structures	30/23-Oct-24	03-Dec-24
<b>100% GMP - Subcontract Award</b>		24/16-Sep-24	17-Oct-24
AWD-2270	Award / Issue Structural Steel Subcontract	10/16-Sep-24	27-Sep-24
AWD-2280	Award / Issue Concrete Subcontract	10/16-Sep-24	27-Sep-24
AWD-2000	Award / Issue Casework Subcontract	10/04-Oct-24	17-Oct-24
AWD-2010	Award / Issue Roofing Subcontract	10/04-Oct-24	17-Oct-24
AWD-2020	Award / Issue Doors, Frames, & Hardware Sul	10/04-Oct-24	17-Oct-24
AWD-2030	Award / Issue Glass & Glazing Subcontract	10/04-Oct-24	17-Oct-24
AWD-2040	Award / Issue Framing, Drywall, and Stucco Si	10/04-Oct-24	17-Oct-24
AWD-2050	Award / Issue Tile Subcontract	10/04-Oct-24	17-Oct-24
AWD-2060	Award / Issue Carpet & Resilient Flooring Subx	10/04-Oct-24	17-Oct-24
AWD-2070	Award / Issue Acoustical Ceilings & Wall Pane	10/04-Oct-24	17-Oct-24
AWD-2080	Award / Issue Painting Subcontract	10/04-Oct-24	17-Oct-24
AWD-2090	Award / Issue Terrazzo Subcontrat	10/04-Oct-24	17-Oct-24
AWD-2100	Award / Issue Specialties Subcontract	10/04-Oct-24	17-Oct-24
AWD-2110	Award / Issue Lockers Subcontract	10/04-Oct-24	17-Oct-24
AWD-2120	Award / Issue Signage Subcontract	10/04-Oct-24	17-Oct-24

 Actual Work  
 Remaining Work  
 Critical Remaini...

City of Clearwater City Hall - 9/16/2024





Start Date: 01-Sep-23  
Finish Date: 01-Sep-26

Page 2 of 13










 Actual Work  Remaining Work  Critical Remaini... Page 72	City of Clearwater City Hall - 9/16/2024	Start Date: 01-Sep-23 Finish Date: 01-Sep-26	Page 4 of 13	
--	--	---	--------------	---



Activity ID	Activity Name	Original	Start	Finish	2024												2025												2026												2027												
					Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun			
SUB-2170	PREPARE & SUBMIT SIGNAGE		20 18-Oct-24	14-Nov-24																																																	
SUB-2830	CM REVIEW & APPR SIGNAGE		7 15-Nov-24	25-Nov-24																																																	
SUB-3060	ARCH/ENG REV & APPR SIGNAGE		15 26-Nov-24	16-Dec-24																																																	
SUB-3520	FAB & DELIVER ACCESS SIGNAGE		20 17-Dec-24	13-Jan-25																																																	
Locker Submittals					82	18-Oct-24	10-Feb-25																																														
SUB-2180	PREPARE & SUBMIT LOCKERS & SPECIAL		20 18-Oct-24	14-Nov-24																																																	
SUB-2840	CM REVIEW & APPR LOCKERS & SPECIAL		7 15-Nov-24	25-Nov-24																																																	
SUB-3070	ARCH/ENG REV & APPR LOCKERS & SPEC		15 26-Nov-24	16-Dec-24																																																	
SUB-3530	FAB & DELIVER LOCKERS & SPECIALTY S		40 17-Dec-24	10-Feb-25																																																	
Specialties Submittals					72	18-Oct-24	27-Jan-25																																														
SUB-2190	PREPARE & SUBMIT MISC. SPECIALTIES		15 18-Oct-24	07-Nov-24																																																	
SUB-2590	CM REVIEW & APPR MISC. SPECIALTIES		7 08-Nov-24	18-Nov-24																																																	
SUB-2950	ARCH/ENG REV & APPR MISC. SPECIALTIE		15 19-Nov-24	09-Dec-24																																																	
SUB-3430	FAB & DELIVER MISC. SPECIALTIES		35 10-Dec-24	27-Jan-25																																																	
Window Blinds Submittals					72	18-Oct-24	27-Jan-25																																														
SUB-2200	PREPARE & SUBMIT WINDOW BLINDS		10 18-Oct-24	31-Oct-24																																																	
SUB-2440	CM REVIEW & APPR WINDOW BLINDS		7 01-Nov-24	11-Nov-24																																																	
SUB-2720	ARCH/ENG REV & APPR WINDOW BLINDS		15 12-Nov-24	02-Dec-24																																																	
SUB-3270	FAB & DELIVER WINDOW BLINDS		40 03-Dec-24	27-Jan-25																																																	
Casework Submittals					87	18-Oct-24	17-Feb-25																																														
SUB-2210	PREPARE & SUBMIT CASEWORK		20 18-Oct-24	14-Nov-24																																																	
SUB-2850	CM REVIEW & APPR CASEWORK		7 15-Nov-24	25-Nov-24																																																	
SUB-3080	ARCH/ENG REV & APPR CASEWORK		15 26-Nov-24	16-Dec-24																																																	
SUB-3540	FAB & DELIVER CASEWORK		45 17-Dec-24	17-Feb-25																																																	
Fire Protection Submittals					62	18-Oct-24	13-Jan-25																																														
SUB-2220	PREPARE & SUBMIT FIRE PROTECTION PI		20 18-Oct-24	14-Nov-24																																																	
SUB-2860	CM REVIEW & APPR FIRE PROTECTION F		7 15-Nov-24	25-Nov-24																																																	
SUB-3090	ARCH/ENG REV & APPR FIRE PROTECTIO		15 26-Nov-24	16-Dec-24																																																	
SUB-3550	FAB & DELIVER FIRE PROTECTION PIPING		20 17-Dec-24	13-Jan-25																																																	
Plumbing Submittals					72	18-Oct-24	27-Jan-25																																														
SUB-2230	PREPARE & SUBMIT PLUMBING MATERIAL		10 18-Oct-24	31-Oct-24																																																	
SUB-2240	PREPARE & SUBMIT PLUMBING PIPING SE		20 18-Oct-24	14-Nov-24																																																	
SUB-2250	PREPARE & SUBMIT PLUMBING FIXTURES		10 18-Oct-24	31-Oct-24																																																	
SUB-2450	CM REVIEW & APPR PLUMBING MATERIAL		5 01-Nov-24	07-Nov-24																																																	
SUB-2460	CM REVIEW & APPR PLUMBING FIXTURES		7 01-Nov-24	11-Nov-24																																																	
SUB-2600	ARCH/ENG REV & APPR PLUMBING MATEF		15 08-Nov-24	28-Nov-24																																																	
SUB-2730	ARCH/ENG REV & APPR PLUMBING FIXTU		15 12-Nov-24	02-Dec-24																																																	
SUB-2870	CM REVIEW & APPR PLUMBING PIPING S		7 15-Nov-24	25-Nov-24																																																	
SUB-3100	ARCH/ENG REV & APPR PLUMBING PIPINC		15 26-Nov-24	16-Dec-24																																																	

[illegible]

 Actual Work  
 Remaining Work  
 Critical Remaini...

Page 74

City of Clearwater City Hall - 9/16/2024


Start Date: 01-Sep-23  
Finish Date: 01-Sep-26

Page 6 of 13



[illegible]



<div> <div></div> Actual Work <div></div> Remaining Work <div></div> Critical Remaini... </div> <div> Page 76 </div>	<div> City of Clearwater City Hall - 9/16/2024 </div>	<div> Start Date: 01-Sep-23  Finish Date: 01-Sep-26 </div>	<div> Page 8 of 13 </div>	<div>  </div>
--	---	--	---------------------------	--

[illegible]


- Actual Work
- Remaining Work
- Critical Remaining Work

City of Clearwater City Hall - 9/16/2024




Start Date: 01-Sep-23  
Finish Date: 01-Sep-26

Page 9 of 13

# Ajax

<div> <div></div> Actual Work <div></div> Remaining Work <div></div> Critical Remaini... </div> <div> Page 78 </div>	<div> City of Clearwater City Hall - 9/16/2024 </div>	<div> Start Date: 01-Sep-23  Finish Date: 01-Sep-26 </div>	<div> Page 10 of 13 </div>	<div>  </div>
--	---	--	----------------------------	--

[illegible]

 Actual Work  
 Remaining Work  
 Critical Remaini...

Page 79

City of Clearwater City Hall - 9/16/2024

Start Date: 01-Sep-23  
Finish Date: 01-Sep-26

Page 11 of 13





18-Dec-25, Back of House Areas

Back of House CMU

Prime & Paint CMU

# Ajax



