

Revised Quote Based on Adding one Size 1 3hp Starter to MCC-3 02/01/2017

Q2C Number: 38847971

Quote Number: 1

Revision Number: 0

Project Name: MARSHALL ST HEADWORKS CLEARWATER**Project Sub-Name:** McKim& Creed Storm Damage**Project Location:** Clearwater, FL**Quote Name:** MARSHALL STREET APCF INFLUENT PUMP**Through Addenda Number:** 0**Bid Date:** 9/12/2016**Consultant / Specifier:****Contractor / Installer:****Sales Representative:** BRENT GIBBS

Conditions of Sale

*This Quotation is subject to Schneider Electric USA, Inc.'s published Conditions of Sale***Payment Terms:** STANDARD**Billing Type(s):****Currency:** US DOLLARS

Quote Markings

Pricing Based on Purchase through Authorized Square D Distributor.

Price includes delivery to site FOB Prepaid Factory.....\$ 38,500 End User Net

Price Excludes Sales Tax.

MCC is NEMA 1A

Quoted per drawings and BOM. No Specs Provided. Revised 02/01/2017

Q2C Number: 38847971

Quote Number: 1

Revision Number: 0

Project Name: MARSHALL ST HEADWORKS CLEARWATER

Quote Name: MARSHALL STREET APCF INFLUENT
PUMP

Item No.	Qty.	Catalog Number / Details
009-00	1	<p>Designation: SWB-12 Square D Custom Swbd Series 2 QED Switchboard</p> <p>-----</p> <p>Square D Custom Swbd Series 2 Designed and Tested in accordance with: UL 891/NATIONAL ELECTRIC CODE/NEMA PB-2 System Voltage - 480Y/277V 3Ph 4W 60Hz Source Description - Main is Remote System Ampacity - 1200A Tin Plated Copper Main Bus Neutral Bus - 100% Max Available Fault Current (RMS) - 65kA Enclosure - Type 1 Accessibility: Front Only Exterior Paint Color - ANSI 49 Ground Lug provided for each device Copper Ground Bus</p> <p>Dimensions</p> <p>-----</p> <p>2 - 36" Wide Section(s) 2 - 24" Deep Enclosure(s) Dimensions: 72.00" W X 24" Max D X 91.5" H Approximate Weight: 1532.00 lbs / 694.92 kgs</p> <p>Incoming Requirements</p> <p>-----</p> <p>UL Dead Front Entry Point: Left of Lineup, Through the Top Connection Type: Cable in Bussed Auxiliary SPD with Surge Rating 240kA SPD Dry Contacts Includes Surge Counter Power Meter - PM5563RD 3 CTs PM5563 w/ Display - 3 phase 4 wire wye 1200A</p> <p>Feeders</p> <p>-----</p> <p>Devices Associated with Remote Main:</p> <p>4 - 400AS/400AT 480V 80% Rated 65 kA 3 Pole UL, Group Mounted Electronic Trip Circuit Breaker: Type LJ 1 - 800AS/400AT 480V 80% Rated 65 kA 3 Pole UL, Group Mounted Electronic Trip Circuit Breaker: Type PJ Kirk Key Interlock 1 - 800AS/600AT 480V 80% Rated 65 kA 3 Pole UL, Group Mounted Electronic Trip Circuit Breaker: Type PJ Common Feeder Features: Standard Trip Unit, Long Time, Instantaneous</p> <p>Estimated days to ship excluding transit: 50 working days after customer release to manufacture. See Conditions of Sale.</p>
010-00	1	<p>Designation: MCC-3 Model 6 LVMCC</p>

Q2C Number: 38847971

Quote Number: 1

Revision Number: 0

Project Name: MARSHALL ST HEADWORKS CLEARWATER

Quote Name: MARSHALL STREET APCF INFLUENT
PUMP

Item No.	Qty.	Catalog Number / Details
		<p>Model 6 MCC - Standard Package</p> <p>-----</p> <p>System Voltage: 480V 3PH 3W 60Hz Max Available Fault Current (RMS) - 65kA Control Power - 120Vac 1/4" x 1" Horizontal Ground Bus, Tin Plated Copper 800A Tin Plated Copper Horizontal Bus Class 1 Type B Wiring 20" Deep Construction 65kA Bus Withstand Rating General Purpose Type 1 Gasketed Enclosure Master Nameplate Engraved with Black Surface/White Letters Standard Exterior Paint ANSI 49 Equipment Mounting Height 72" Manual Vertical Bus Shutters Stainless Steel Nameplate Screws Unit Nameplate Engraved with Black Surface / White Letters Rodent Barriers Engineer To Order (ETO-L) Engineered To Order (ETO) 3 - Section(s) with 300A Tin Plated Copper Vertical Bus</p> <p>DIMENSIONS AND WEIGHT</p> <p>-----</p> <p>Dimensions: 60.00"W X 20"D X 94.5"H Approximate Weight: 2250.00 lbs / 1020.60 kgs</p> <p>INCOMING</p> <p>-----</p> <p>Incoming Connection: Cable SPD Surge Counter SPD 240kA Surge Rating for Wye Secondary Transformer - with disconnect</p> <p>MAIN</p> <p>-----</p> <p>Main Lugs Top Entry 800A</p> <p>FULL VOLTAGE NON-REVERSING STARTERS</p> <p>-----</p> <p>1 - 40 HP NEMA Size 3 FVNR Starter w/Circuit Breaker Control Power Transformer 150VA 3 - 2 HP NEMA Size 1 FVNR Starter w/Circuit Breaker Control Power Transformer 100VA Motor On LED Pilot Light Red 2 - 10 HP NEMA Size 1 FVNR Starter w/Circuit Breaker Control Power Transformer 100VA Motor On LED Pilot Light Red 1 - 1/4 HP NEMA Size 1 FVNR Starter w/Circuit Breaker Control Power Transformer 100VA Motor On LED Pilot Light Red 1 - 3 HP NEMA Size 1 FVNR Starter w/Circuit Breaker Control Power Transformer 100VA Motor On LED Pilot Light Red</p>

Q2C Number: 38847971

Quote Number: 1

Revision Number: 0

Project Name: MARSHALL ST HEADWORKS CLEARWATER

Quote Name: MARSHALL STREET APCF INFLUENT
PUMP

Item No.	Qty.	Catalog Number / Details
		COMMON FULL VOLTAGE NON-REVERSING FEATURES ----- Electronic Motor Circuit Protector #16 AWG MTW Control Wire 65kA Interrupting Rating Melting Alloy Overload Relay 30mm Type K Pilot Devices Hand-Off-Auto Selector Switch
		FEEDERS ----- 1 - Compac 6 Circuit Breaker Branch Feeder 100A 65kA Interrupting Rating 2 - Compac 6 Circuit Breaker Branch Feeder 50A 65kA Interrupting Rating 3 - Compac 6 Circuit Breaker Branch Feeder 30A 65kA Interrupting Rating 1 - Compac 6 Circuit Breaker Branch Feeder 40A 65kA Interrupting Rating 1 - Compac 6 Circuit Breaker Branch Feeder 20A 65kA Interrupting Rating
		MISCELLANEOUS DEVICES ----- 1 - Surge Protection Device 3 - 12" Prepared Space 1 - 18" Prepared Space

Estimated days to ship excluding transit: 35 working days after customer release to manufacture. See Conditions of Sale.