

MORNINGSIDE MAIN POOL RESURFACING					
BID OPENING - 2/21/18 - 2:00 PM AWARD - THURSDAY, 03/15/18					
				The Pool Works of Florida, Inc. 9191 130th Ave. N. Largo, FL 33773	
	BID ITEMS	QTY	UNIT	UNIT PRICE	AMOUNT
1	Mobilization & demobilization	1	LS	\$ 2,000.00	\$ 2,000.00
2	Remove, restore, protect and reinstall all fixtures including diving boards, railings, ladders, any removable stairs, and backsroke poles. Protect all existing tiles, depth markers and 'no diving' markers. Perform leak test with report and drain pool. Remove pool plug and install sump pumps. Removal and restoration of existing tiles and expansion joints.	1	LS	\$ 5,560.00	\$ 5,560.00
3	Sound pool with chain to identify low spots and mark with paint. Chip away existing surface at hollow spots clean away loose material, prepare to receive bond coat, provide fill material as required ready for final bond coat and Hydrazzo finish surface.	2,500	Sq. F.	\$ 3.00	\$ 7,500.00
4	Remove existing surface around existing pool tiles via hydro-blasting, sand blasting, or industry method and means to a depth of 3/8". Fill areas where existing surface has been removed prior to installing Hydrazzo surface. Prepare remaining pool surfaces per specifications per sheet 5 of 5 to accept Hydrazzo surfacing manufacture's recommendations	1	LS	\$ 6,138.00	\$ 6,138.00
5	Provide Hayward SP1010 socket fitting including drain cover for replacement if damaged during pool surfacing removal	35	EA	\$ 100.00	\$ 3,500.00
6	Remove and replace main drain	3	EA	\$ 300.00	\$ 900.00
7	Remove & replace floor returns inlets	14	EA	\$ 100.00	\$ 1,400.00
8	Remove and replace wall return inlets	6	EA	\$ 216.67	\$ 1,300.02
9	Remove & replace pool level fixture	1	EA	\$ 100.00	\$ 100.00
10	Remove & replace gutter drains Pool Contractor provide leak test detection test report to Owner & review report with Owner to determine if leaks are within the pool-shell. If determined leak is below the pool shell no repairs shall be made but recored for future repairs under a different contract in the future. Any gutter drains show no signs of leak no repairs shall be made.	35	EA	\$ 100.00	\$ 3,500.00
11	Remove and replace vacuum fittings	3	EA	\$ 100.00	\$ 300.00
12	Perform Hydrostatic Test	1	LS	\$ 1,000.00	\$ 1,000.00
13	Replace bull nose tiles back of pool gutter beam with black glazed tile bull nose tiles. Back of pool gutter tiles do not need to be nonslip tiles.	1	LS	\$ 5,100.00	\$ 5,100.00
14	Replace bull nose perimeter pool water line tile with black non-slip bull nose tiles and must meet Wet DCOF testing of non-slip tiles	1	LS	\$ 6,678.00	\$ 6,678.00
15	Clean all surfaces prior to installing the bonding agent. Apply bonding agent. Install Hydrazzo surface according to manufacture's specifications. Clean new surface to prepare for pool filling.	1	LS	\$ 48,665.00	\$ 48,665.00
16	Fill pool, brush, acid wash, and polish new surface. Balance pool chemicals five days prior to Pinellas County Health Department Inspection. Pool chemicals to be provided by Owner. Contact Pinellas County Health Department for inspection and certify pool for operation. Provide Certificate of Operation to Owner. Close out permit. Provide close-out materials package to Owner. Site cleanup.	1	LS	\$ 2,500.00	\$ 2,500.00
17	General Conditions (see Section IV Scope of Work	1	LS	\$ 850.00	\$ 850.00
18	Subtotal (ITEMS 1-17)				\$ 96,991.02
40	10% Contingency				\$ 9,699.10
41	TOTAL BID (ITEMS 1-17 plus Contingency)				\$ 106,690.12